

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

WESTGATE OIL CO.
Johnson No. 1

SEC. 17 T. 21 R. 7W.
NE SE NE

Total Depth. 3390
Comm. 2-10-37 Comp. 3-11-37
Shot or Treated.
Contractor. E. K. Carey.
Issued. 4-10-37

County Rice.



CASING. Rotary to 3366
cable 3390

12 1/2" 115'
7" 3366'
53/16" 3386

Elevation. 1618

Production. Pot. 1899 B.

Figures Indicate Bottom of Formations.

sand and red rock	115
shale and shells	650
salt	940
lime and shale	1052
shale	1095
broken lime	1230
lime	1330
shale and lime shells	1368
lime shells	1495
shale and shells	1515
lime	1615
shale and shells	1757
broken lime	1990
shale	2083
shale and shells	2145
shale and lime	2262
lime	2285
shale	2305
broken lime	2334
shale and lime	2372
lime	2426
broken lime	2445
lime	2660
broken lime	2672
lime	2780
shale	2895
lime	3010
shale	3015
lime	3268
shale and lime shells	3330
lime shale	3366
standard tools.	
shale grey	3374
conglomerate	3390

Total Depth.

Kansas City Top 2930.
Conglomerate 3374-3390 oil 3380-86 flowing.

Halliburton steel line Meas. taken at 2000' and 3000' checked
within 6" of drill pipe Meas.