

WELL LOG BUREAU-- KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- THOMAS ALLAN & COOPERATIVE REFG. ASSN.
Farm- Johnson No. 1

SEC. 2 T. 21 R. 7W
CN/2 NW SE

Total Depth. 3423
Comm. 3-26-55 Comp. 4-15-55
Shot or Treated.
Contractor. Tom Allan
Issued. 5-21-55

County Rice

KANSAS



CASING:
8 5/8" 160' cem w/130 sx, Circ,
5 1/2" 3406' cem w/ 75 sx

Elevation 1652 RB

Production. Swab 2 1/2 BO/hr.

All Depth from Rotary Bushings Figures Indicate Bottom of Formations

soil, sand	20
clay hellow	95
red beds	580
shale gray	710
salt, shale	1010
anhydrite	1140
shale	1280
lime	1430
shale	1470
lime	1520
lime, shale	1630
lime	1730
lime, shale	1990
shale, shells	2560
lime	2780
shale, sand	2950
lime w/shale breaks	3310
shale, shells	3403
sand Congl. (RTD)	3407
CHANGED TO CABLE TOOLS	
sandstone & red shale	3410
Vari color Chert,	
gravel & sand	
825' of oil in 3 hrs.	3419
sandy red mud	3419
vari color chert, gravel	
Swab 6 BO 4th tour	
Water Frac	
11,500 gal. water &	
3300# sand	
Swab 21 BO 6th tour	3423
Total Depth	

Tops:

Est. Lansing	2945
Conglomerate	3403