

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- HENRY BENNETT
Farm- Nelson No. 1

SEC. 12 T. 21 R. 7W
CN $\frac{1}{2}$ SW

3443'

Total Depth. 3443'
Comm. 12-17-55 Comp. 12-30-55
Shot or Treated.
Contractor. Salina Drlg. Corp., Inc.
Issued. 8-25-56

County Rice KANSAS



CASING:
8 5/8" 147' w/140 sx cem
5 1/2" 3401 1/2' w/75 sx cem.

Elevation. 1632' DF

Production. Dry

Figures indicate Bottom of Formations.

surface soil-sand-red bed 70
shale-shells 655
red bed-shale 990
shale-lime 1360
lime 1422
shale-lime 1780
lime 1850
shale-lime 2565
lime 2703
lime-shale-sand 2805
lime-shale 3000
lime 3065
lime-shale 3120
lime 3275
lime-shale 3400
Conglomerate 3404
Conglomerate 3407 RTD
Drilled down Rainbow show
1' under the pipe, drilled
2 more feet no increase,
drilled down to 3443
Total Depth

TOPS:
Heebner 2707
Toronto 2723
Douglas 2726
Lansing 2932
Conglomerate 3400

Perf. fr 3395-3401' & fractured
w/3000# sand.

Installed tbgs. & rods & after
pumping 1 bbl. oil per day was
abandoned.