


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- SEROBEE DRILLING CO.
Farm- Bauer No. 1

SEC. 23 T. 21 R. 7W
C N/2 NE SW

Total Depth. 3415'
Comm. 2-23-59 Comp. 3-6-59
Shot or Treated.
Contractor. SeRoBee Drlg.
Issued. 3-15-59

County Rice
KANSAS



CASING:
3 5/8" 198' cem w/100 sx.
5 1/2" 3407' cem w/60 sx.

Elevation. 1599' RB

Production. 25 BOPD

Figures Indicate Bottom of Formations.

sand	70
red bed & shells	198
red rock	215
shale & red bed	640
shale, shell, salt,	
lime	1015
shells & shale	1150
lime & shale	2400
lime	2660
lime & shale	2720
sand	2791
sandy lime & shale	2885
lime	3284
lime & shale	3401
Conglomerate	3406
Mississippi lime	3415 RTD
Total Depth	

TOPS:	
Heebner	2697
Toronto	2713
Douglas	2719
Brown Lime	2883
Lansing	2900
Base Kansas City	3262
Shaley Conglomerate	3385
Cherty Conglomerate	3397
Mississippi Cherts	3406

DST #1 3406-3410', op 1 hr., rec. 20'
slightly oil cut mud, BHSIP 240#/20 mins.

DST #2 3408-3415', op 1 hr., rec. 2400'
of gas, 150' of fluid, (30' of HOCM, 115'
of oil, 5' of water). IFP 85#, FFP 170#,
BHSIP 945#/20 mins.