
15-159-22578 35-21s-8w



TRILOBITE TESTING, INC.

DRILL STEM TEST REPORT

Prepared For: **American Warrior**

PO Box 399
Garden City KS 67846

ATTN: MarcDowning

35 21S 8W Rice KS

Bull Creek # 1-35

Start Date: 2008.07.22 @ 00:24:47
End Date: 2008.07.22 @ 07:05:47
Job Ticket #: 29330 DST #: 1

15-159-22578
SW SE NW NE
1280 FNL 1700 FEL

American Warrior
Bull Creek # 1-35
35 21S 8W Rice KS
DST # 1
Conglomerate
2008.07.22

Trilobite Testing, Inc
PO Box 1733 Hays, KS 67601
ph: 785-625-4778 fax: 785-625-5620

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 26 2008
CONSERVATION DIVISION
WICHITA, KS

DRILL STEM TEST REPORT

American Warrior

PO Box 399
Garden City KS 67846

ATTN: MarcDowning

Bull Creek # 1-35

35 21S 8W Rice KS

Job Ticket: 29330 **DST#: 1**

Test Start: 2008.07.22 @ 00:24:47

GENERAL INFORMATION:

Formation: **Conglomerate**
Deviated: No Whipstock: ft (KB)
Time Tool Opened: 02:13:17
Time Test Ended: 07:05:47

Test Type: Conventional Bottom Hole
Tester: Jerry Adams
Unit No: 45


Interval: 3320.00 ft (KB) To 3380.00 ft (KB) (TVD)
Total Depth: 3380.00 ft (KB) (TVD)
Hole Diameter: 7.88 inches Hole Condition: Fair

Reference Elevations: 1628.00 ft (KB)
1620.00 ft (CF)
KB to GR/CF: 8.00 ft

Serial #: 6798 **Inside**
Press@RunDepth: 297.38 psig @ 3321.00 ft (KB)
Start Date: 2008.07.22 End Date: 2008.07.22
Start Time: 00:24:48 End Time: 07:05:47

Capacity: 7000.00 psig
Last Calib.: 2008.07.22
Time On Btm: 2008.07.22 @ 02:11:47
Time Off Btm: 2008.07.22 @ 05:14:17

TEST COMMENT: IF Weak blow built to 5 1/4 " decreased to 4 "
ISI No blow
FF Weak blow built to 6 " decreased to 2 "
FSI No blow



PRESSURE SUMMARY

Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	1660.79	101.54	Initial Hydro-static
2	214.21	101.27	Open To Flow (1)
49	296.94	101.76	Shut-In(1)
91	297.28	102.27	End Shut-In(1)
92	172.46	102.20	Open To Flow (2)
138	297.38	103.43	Shut-In(2)
181	297.56	104.22	End Shut-In(2)
183	1634.30	105.05	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
110.00	VSWCM 5%W 95%M	1.54
0.00	RW= .237 @ 74 deg.	0.00
0.00		0.00

Gas Rates

	Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)

DRILL STEM TEST REPORT

TOOL DIAGRAM

American Warrior

PO Box 399
Garden City KS 67846

ATTN: MarcDowning

Bull Creek # 1-35

35 21S 8W Rice KS

Job Ticket: 29330 **DST#: 1**

Test Start: 2008.07.22 @ 00:24:47

Tool Information

Drill Pipe:	Length:	3317.00 ft	Diameter:	3.80 inches	Volume:	46.53 bbl	Tool Weight:	2700.00 lb
Heavy Wt. Pipe:	Length:	0.00 ft	Diameter:	0.00 inches	Volume:	0.00 bbl	Weight set on Packer:	20000.00 lb
Drill Collar:	Length:	0.00 ft	Diameter:	0.00 inches	Volume:	0.00 bbl	Weight to Pull Loose:	70000.00 lb
					Total Volume:	46.53 bbl	Tool Chased	0.00 ft
Drill Pipe Above KB:		25.00 ft					String Weight: Initial	45000.00 lb
Depth to Top Packer:		3320.00 ft					Final	46000.00 lb
Depth to Bottom Packer:		ft						
Interval between Packers:		60.00 ft						
Tool Length:		88.00 ft						
Number of Packers:		2	Diameter:	6.75 inches				

Tool Comments:

Tool Description	Length (ft)	Serial No.	Position	Depth (ft)	Accum. Lengths	
Shut In Tool	5.00			3297.00		
Hydraulic tool	5.00			3302.00		
Jars	5.00			3307.00		
Safety Joint	3.00			3310.00		
Packer	5.00			3315.00	28.00	Bottom Of Top Packer
Packer	5.00			3320.00		
Stubb	1.00			3321.00		
Recorder	0.00	6798	Inside	3321.00		
Recorder	0.00	8358	Inside	3321.00		
Perforations	18.00			3339.00		
Change Over Sub	1.00			3340.00		
Blank Spacing	31.00			3371.00		
Change Over Sub	1.00			3372.00		
Perforations	5.00			3377.00		
Bullnose	3.00			3380.00	60.00	Bottom Packers & Anchor
Total Tool Length:	**88.00**					

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 26 2008
CONSERVATION DIVISION

TRILOBITE TESTING, INC

DRILL STEM TEST REPORT

FLUID SUMMARY

American Warrior

PO Box 399
Garden City KS 67846

ATTN: MarcDowning

Bull Creek # 1-35

35 21S 8W Rice KS

Job Ticket: 29330 **DST#: 1**

Test Start: 2008.07.22 @ 00:24:47

Mud and Cushion Information

Mud Type:	Gel Chem	Cushion Type:		Oil API:	deg API
Mud Weight:	9.00 lb/gal	Cushion Length:	ft	Water Salinity:	28000 ppm
Viscosity:	49.00 sec/qt	Cushion Volume:	bbl		
Water Loss:	11.18 in³	Gas Cushion Type:			
Resistivity:	0.00 ohm.m	Gas Cushion Pressure:	psig		
Salinity:	10000.00 ppm				
Filter Cake:	0.20 inches				

Recovery Information

Recovery Table


Length ft	Description	Volume bbl
110.00	VSWCM 5%W 95%M	1.543
0.00	RW= .237 @ 74 deg.	0.000
0.00		0.000

Total Length: 110.00 ft Total Volume: 1.543 bbl


Num Fluid Samples: 0 Num Gas Bombs: 0 Serial #: none

Laboratory Name: Laboratory Location:

Recovery Comments:



RECEIVED
KANSAS CORPORATION COMMISSION
AUG 2 6 2008
CONSERVATION DIVISION



TRILOBITE TESTING, INC.

DRILL STEM TEST REPORT

Prepared For: **American Warrior**

PO Box 399
Garden City KS 67846

ATTN: MarcDowning

35 21S 8W Rice KS

Bull Creek # 1-35

Start Date: 2008.07.22 @ 20:28:13
End Date: 2008.07.23 @ 02:38:43
Job Ticket #: 29331 DST #: 2

Trilobite Testing, Inc
PO Box 1733 Hays, KS 67601
ph: 785-625-4778 fax: 785-625-5620

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 26 2008

TRILOBITE TESTING, INC

DRILL STEM TEST REPORT

American Warrior

PO Box 399
Garden City KS 67846

ATTN: MarcDowning

Bull Creek # 1-35

35 21S 8W Rice KS

Job Ticket: 29331 **DST#: 2**

Test Start: 2008.07.22 @ 20:28:13

GENERAL INFORMATION:

Formation: **Mississippi**
Deviated: No Whipstock: ft (KB)
Time Tool Opened: 21:50:43
Time Test Ended: 02:38:43

Test Type: Conventional Straddle
Tester: Jerry Adams
Unit No: 45


Interval: 3388.00 ft (KB) To 3408.00 ft (KB) (TVD)
Total Depth: 3484.00 ft (KB) (TVD)
Hole Diameter: 7.88 inches Hole Condition: Fair

Reference Elevations: 1628.00 ft (KB)
1620.00 ft (CF)
KB to GR/CF: 8.00 ft

Serial #: 8358 **Inside**
Press@RunDepth: 26.20 psig @ 3389.00 ft (KB)
Start Date: 2008.07.22 End Date: 2008.07.23
Start Time: 20:28:14 End Time: 02:38:43

Capacity: 7000.00 psig
Last Calib.: 2008.07.23
Time On Btm: 2008.07.22 @ 21:43:43
Time Off Btm: 2008.07.23 @ 00:45:13

TEST COMMENT: IF Fair blow BOB in 11 mins.
ISI No blow
FF Fair blow BOB in 14 mins.
FSI No blow



PRESSURE SUMMARY

Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	1709.52	105.88	Initial Hydro-static
7	15.60	106.18	Open To Flow (1)
46	22.84	106.69	Shut-In(1)
90	207.27	106.98	End Shut-In(1)
91	20.98	107.16	Open To Flow (2)
135	26.20	107.52	Shut-In(2)
180	194.47	107.77	End Shut-In(2)
182	1640.13	108.52	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
30.00	VSGOCM 4%G 2%O 94%M	0.42
0.00	270 ' GIP	0.00
0.00		0.00

Gas Rates

	Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)

DRILL STEM TEST REPORT

TOOL DIAGRAM

American Warrior

PO Box 399
Garden City KS 67846

ATTN: MarcDowning

Bull Creek # 1-35

35 21S 8W Rice KS

Job Ticket: 29331 **DST#: 2**

Test Start: 2008.07.22 @ 20:28:13

Tool Information

Drill Pipe:	Length:	3381.00 ft	Diameter:	3.80 inches	Volume:	47.43 bbl	Tool Weight:	2800.00 lb
Heavy Wt. Pipe:	Length:	0.00 ft	Diameter:	0.00 inches	Volume:	0.00 bbl	Weight set on Packer:	20000.00 lb
Drill Collar:	Length:	0.00 ft	Diameter:	0.00 inches	Volume:	0.00 bbl	Weight to Pull Loose:	52000.00 lb
					Total Volume:	47.43 bbl	Tool Chased	0.00 ft
Drill Pipe Above KB:		21.00 ft					String Weight: Initial	48000.00 lb
Depth to Top Packer:		3388.00 ft					Final	48000.00 lb
Depth to Bottom Packer:		3408.00 ft						
Interval betw een Packers:		20.00 ft						
Tool Length:		127.00 ft						
Number of Packers:		3	Diameter:	6.75 inches				

Tool Comments:

Tool Description	Length (ft)	Serial No.	Position	Depth (ft)	Accum. Lengths	
Shut In Tool	5.00			3365.00		
Hydraulic tool	5.00			3370.00		
Jars	5.00			3375.00		
Safety Joint	3.00			3378.00		
Packer	5.00			3383.00	28.00	Bottom Of Top Packer
Packer	5.00			3388.00		
Stubb	1.00			3389.00		
Recorder	0.00	8358	Inside	3389.00		
Perforations	18.00			3407.00		
Recorder	0.00	13249	Outside	3407.00		
Blank Off Sub	1.00			3408.00	20.00	Tool Interval
Packer	4.00			3412.00		
Stubb	1.00			3413.00		
Perforations	7.00			3420.00		
Change Over Sub	1.00			3421.00		
Recorder	0.00	6798	Inside	3421.00		
Blank Spacing	62.00			3483.00		
Change Over Sub	1.00			3484.00		
Bullnose	3.00			3487.00	79.00	Bottom Packers & Anchor
Total Tool Length:	**127.00**					

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 26 2008
CONSERVATION DIVISION

TRILOBITE TESTING, INC

DRILL STEM TEST REPORT

FLUID SUMMARY

American Warrior

PO Box 399
Garden City KS 67846

ATTN: MarcDow ning

Bull Creek # 1-35

35 21S 8W Rice KS

Job Ticket: 29331 **DST#: 2**

Test Start: 2008.07.22 @ 20:28:13

Mud and Cushion Information

Mud Type:	Gel Chem	Cushion Type:		Oil API:	deg API
Mud Weight:	9.00 lb/gal	Cushion Length:	ft	Water Salinity:	ppm
Viscosity:	49.00 sec/qt	Cushion Volume:	bbl		
Water Loss:	12.79 in³	Gas Cushion Type:			
Resistivity:	0.00 ohm.m	Gas Cushion Pressure:	psig		
Salinity:	10000.00 ppm				
Filter Cake:	0.20 inches				

Recovery Information

Recovery Table


Length ft	Description	Volume bbl
30.00	VSGOCM 4%G 2%O 94%M	0.421
0.00	270 ' GIP	0.000
0.00		0.000

Total Length: 30.00 ft Total Volume: 0.421 bbl

Num Fluid Samples: 0 Num Gas Bombs: 0 Serial #: none

Laboratory Name: Laboratory Location:

Recovery Comments:



RECEIVED
KANSAS CORPORATION COMMISSION
AUG 2 6 2008
CONSERVATION DIVISION