


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bk Bldg., Wichita, Kansas.

D. R. LAUCK
Heter No. 1.

SEC. 1 T. 21 R. 8W
SE NE SE

Total Depth. 3354½
Comm. 5-25-37 Comp. 6-20-37
Shot or Treated. 30 Qts. 3346-3354 6-20-37
Contractor.
Issued. 7-17-37

County. Rice



CASING:
15" 96'
6" 3341'

Elevation.

Production. Pot. 582 B.

Figures Indicate Bottom of Formations.

sand	55
gumbo	72
sand, shale & shells	96
red rock	210
shale	315
shale & shells	420
shale & red rock	510
shale & shells	700
shale & salt	850
shale & shells	1110
lime & shale	1240
lime	1300
shale	1370
brkn lime	1425
shale	1645
shale & shells	1760
shale	1800
lime	1865
shale & shells	2215
shale	2330
lime	2390
shale	2430
brkn lime	2525
lost circulation at	2503
lime	2640
brkn lime sdy	2670
lime	2765
brkn lime	2800
shale	2875
shale & shells	2930
lime	3010
lime porous	3016
lime	3030
lime porous	3088
lime	3095
shale	3105
lime	3120
brkn lime	3175
lime	3250
lime & shale	3330
SIM at 3300 O.K.	
shale	3342
conglomerate sh oil	3344
3342-3341 derrick floor	
Standardized	
bottom cement	3341
cleaned out	3342½
2600 oil 10 hrs after	
drilling plug and while	
cleaning out and bailing	
conglomerate	3350½
conglomerate with sdy	
shale green and trace	
shale sdy rod	3352½
swab 9 bbls hour	
conglomerate	3354½
inc sdy red shale	
Total Depth.	