


*Plotted*

GERBRAND-PULSE OIL & DRILG.CO.  
 Partington No. 2.

SEC. 22 T. 21 R. 9W  
 SE NW SW

Total Depth. 3330'  
 Comm. 10-10-39 Comp. 10-30-39  
 Shot or Treated.  
 Contractor.  
 Issued. 11-18-39

County. Rice



CASING:  
 10" 102'  
 5 1/2" 3318'

Elevation.

Production. 6,000,000 Gas.  
 Estimated

Figures Indicate Bottom of Formations.

surface, sand & red rock	102
shale	160
shale & shells	245
anhydrite	265
red shale & shells	640
shale & salt	1070
lime brkn	1360
lime	1485
sand	1517
sdv lime	1555
lime	1690
shale & shells	2330
shale	2385
shale & shells	2440
sdv lime	2491
lime	2520
shale & shells	2550
shale	2570
shale & shells	2605
sdv lime	2710
lime brkn	2785
lime	2820
shale & shells	2965
shale	2975
lime	3268
var.col.shale	3288
lime	3305
sand	3306
var.col.shale	3318
sand	3330
Total Depth.	