

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - W.E. RENNIE & SHARON DRG.CO., INC.
Farm - Small No. 1.

SEC. 22 T. 21 R. 9 W
CSE NW

DEEPENING RECORD

Total Depth. 3363'
Comm. 2-25-41 Comp. 3-27-41
Shot or Treated.
Contractor.
Issued. 2-10-45

County. Rice
KANSAS



CASING:
8" 100'
4 1/2" 3313'

Elevation. _____

Production. 3,962,000 G.
R.P. 913#

Figures Indicate Bottom of Formations.

sand 40
red rock 250
anhydrite 270
shale & shells 910
salt & shale 1080
shale & shells 1135
anhydrite & lime 1160
shale & lime 1470
sdy lime 1524
shale & lime 1650
lime brkn 1750
lime 1785
lime & red rock 1800
shale & shells 1920
shale 2160
lime & shale 2330
shale 2485
lime 2500
shale 2565
lime 2725
lime brkn 2835
shale & shells 2982
lime 3248
shale & shells 3313
Misener sand 3314

Put on pmp & wouldn't pmp
Flow 10 to 15 BOPD & 1/2
Mil.ft of gas

DEEPENING RECORD:

Comm. 9-18-44; Comp. 10-9-44
I. P. 1/2 Mil. gas &
5 to 10 BOPD

sand 3338-55
Maquoketa dol. 3363
Total Depth.

No inc. in gas, oil, no wtr
9-25-44 shot 60 qts. from
3320-63

No inc. in oil or gas

Cable Log
sand 3314-3323 1/2
Total Depth.

Gauged 3,718,000 gas be-
fore perforated
Perforated 24 shots 3313 1/2-23
Gauged 3,838,000 gas after
perforating

DEEPENING RECORD:

Sharon Drlg. Co.

Comm. 5-20-44; Comp. 6-6-44
I. P. - 15 BO to 1/2 Mil. G.

sand, inc. in gas 3323-26
sand, sh oil 3333
sand, inc. in oil 3338
Total Depth.

Gauged 814,000 gas @ 3331
" 814,000 gas @ 3333
" 814,000 gas @ 3338
Well started spraying oil
@ 3335
Sprayed 30 gal. oil per hr
@ 3338

5-24-44
Shot 20 Qts. 3322-36
Cleaned out hole, swbd to
btm & swbd down; Swbd 4 1/2
BOPH for 4 hr on 5-29-44