

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - SHARON DRIG.CO.,INC.
Farm - Currie No. 1.

SEC. 22 T. 21 R. 9 W
NW SW NE

Total Depth. 3478' PB 3366'
Comm. 8-14-44 Comp. 9-15-44
Shot or Treated.
Contractor. Sharon Drlg.Co.,Inc.
Issued. 10-7-44

County. Rice
KANSAS



CASING:
8 5/8" 105' Cem.
5 1/2" 3331' Cem.

Elevation. _____

Production. Dry

Figures Indicate Bottom of Formations.

sand	0-46
red bed	243
anhydrite	260
shale & shells	740
salt & shale	980
shale & shells	1275
lime brkn	1815
shale	1830
lime brkn	1856
shale & shells	2240
shale & lime	2315
shale & shells	2395
shale & lime	2450
shale sdy	2493
lime	2848
shale	2858
lime	2898
shale	2923
lime	3052
lime sft	3065
lime	3278
shale & lime shells	3325
shale	3331
shale sand	3334
sand (Rotary TD)	3336
sand	3366
lime	3464
sand	3474
wtr sand	3478
Total Depth	
P.B.	3366

Geol. Tops:
Topeka 2493
Heebner 2791
Base Oread 2844
Brown Ls 2923
Lansing 2954
Spongy fossiliferous sft ls.
pin-point por.excellent odor &
rainbow 3000-03
Oolitic por no shows 3052-63
Base K.C. 3267
Misener sand 3331
Maquoketa limey
dolomite 3366
Viola lime 3408
Simpson shale 3464
Simpson sand 3465
HFW in Simpson
sand 3474-78

Shot 40 qts.solified 3339-66
1/4 BO & 1 1/3 BWFH & show of gas
Gravity of oil 35
Perf. 12 shots 3325-36
no increase.
Set Lane-Wells plug 3050
Perf. 62 shots 2989-3074-no show
500 Acid-show free oil
Reacidized 2000 Gals. - no increase in oil.