


SCHNEIDER - SHELL PETRO.  
Wellman No. 1.

SEC. 22 T. 21 R. 9W  
SW SW SW  
330' fr WL 330' fr SL SW  $\frac{1}{4}$

Total Depth. 3325'  
Comm. 7-31-37 Comp. 10-28-37  
Shot or Treated.  
Contractor. Claude Pulse  
Issued. 11-20-37

County. Rice



Cable O-3325

CASING:

16" 55'  
13" 1194'  
10" 2016'  
8" 2739'  
7" 3315'

Elevation.

Production. 22,481,000 G.

Figures Indicate Bottom of Formations.

sand	55	lime sholls & shale	1740	shale	2905
sdv red rock	210	red rock	1745	lime & shale	2915
red rock	240	lime	1785	lime	2920
brkn lime	250	red rock	1790	shale	2930
red rock	285	lime	1800	rod rock	2940
red rock & shells	325	sholls & red rock	1819	lime (lgt sh oil	3055
red rock	565	bad cave 1790		sdv lime 3000-10)	3065
slate blue	635	lime & shale brks	1827	lime 2BWH 3055-65	3110
red rock	660	lime	1838	lime hrd	3125
shale blue	680	slate	1845	lime 1BWH 3100-10	3142
slate blue	720	lime	1855	shale	3145
slateblue & shells	775	rod rock	1865	lime hrd	3155
shale blue	780	lime	1880	lime	3255
lime	785	shale	1885	rod rock	3260
salt hrd	795	lime hrd	1910	lime	3268
shale blue	805	2 BWH 1895-1905		lime sholls & shale	3300
salt	815	lime	1932	lime-hole caving	3308
salt hrd	840	blue slato & lime sholls	1980	lime hrd	3310
salt	1105	red rock	2000	lime	3316
slate	1115	slate	2012	sdv lime	3317
salt	1125	lime	2025	Encountered gas (est)	
slate & shells	1137	slate	2030	2 to 3 million	3316-17
lime	1145	shale blue	2045	conglomerate	3325
slate & lime	1155	lime	2060	Total Depth.	
red rock	1160	slate	2065		
lime	1165	red rock	2085		
slate	1169	lime	2090	Increase in gas 3317-3325	
shale lgt	1178	brkn lime	2100	Gauged in excess of 20	
lime	1185	shale drk	2110	million cu ft. Est 25	
lime & brkn slate	1210	red rock	2120	to 30 million cu ft gas.	
lime	1220	shale	2145		
shale brkn	1225	shale blue	2165		
lime	1240	lime hrd	2185		
lime & shale brks	1255	shale brown	2215		
lime	1260	shale grey	2230		
lime & slate brks	1340	lime	2250		
lime	1385	lime & shale brks	2269		
red rock	1405	lime	2290		
brkn lime	1495	red rock	2302		
lime 2BWH 1510-25	1535	lime	2325		
slate blue	1540	slate blue	2330		
lime	1545	lime	2335		
red rock	1551	brkn lime	2360		
lime	1562	shale blue	2385		
slate blue	1570	lime	2453		
lime & slate brks	1610	shale	2465		
slate	1625	lime HFW 2487	2544		
lime & slate	1630	lime hrd	2556		
shale	1635	lime HFW 2645-2655	2645		
red rock	1645	lime sdv	2655		
lime	1650	lime	2707		
red rock	1655	lime sdv	2719		
lime	1660	lime	2765		
shale blue	1665	lime hrd	2775		
red rock	1670	lime	2785		
lime hrd hole caving	1690	shale blk	2790		
lime	1695	shale & shells	2800		
red rock	1710	lime	2820		
lime	1725	brkn lime	2850		