


UNION NATIONAL BANK BLDG WICHITA KANSAS

Location NE corner.

Sec. 29 T. 21 R. 9W.

Casing Record

10" 1830 Farm- Wellman No. 1
 20" 54 8 1/4" 2415 Company- Gypsy, United & Stearns-Streeter Co.
 15 1/2" 428 65/8" 2996 Contr.- Lassen & Simmsn.
 12 1/2" 1185 53/16" 3435' Comm.- 8/8/30 Comp.- 12/10/30
 Total Depth 3553' Shot Quarts Between
 Correspondence Regarding This Well Should Be Referred to



Figures Indicate Bottom of Formations.
 Date Issued. 12/20/1930'.

Initial Production Dry.

Elevation

Formation	Depth	Formation	Depth	Formation	Depth
cellar	45	lime hrd	1835	lime hrd	2570
red rock	55	shale lgt	1840	lime mud brown	2575
sand	60	shale drk	1860	UR 8 1/4" to 2520	
red rock	265	shale grey	1885	1 1/2 BW hr at 2575'	
lime	280	red rock	1890	lime hrd grey	2605
red rock	380	lime grey	1895	lime sdy	2615
slate blue	410	lime brkn	1918	lime grey	2655
slate grey	428	2 1/2 BW Hr 1894-1915'		lime white	2670
shale blue	445	shale blue & shells		lime grey	2685
red rock	585	hrd	1935	HPW 2655 to 2670'	
slate blue	760	lime hrd	1955	lime hrd	2702
shale blue	805	shale drk	1975	shale	2705
salt	815	shale black	1980	lime brkn	2714
shale	825	shale lgt	1985	water sand	2734
salt	1000	shale grey	2005	lime hrd	2745
salt rock	1080	shale blue	2008	HPW 2715-30	
salt	1128	lime	2010	water sand	
shale blue	1145	shale drk	2032	lime hrd drk	2770
shale lgt	1215	lime hrd	2042	UR 8 1/4" to 2762'	
lime	1225	shale	2045	lime very hrd	2785
shale & shells	1295	Hole caving		lime grey	2795
shale blue sdy	1315	shale drk	2075	lime brown	2800
shale lgt	1345	Bailing water		lime grey	2810
sdly shale	1375	lime	2083	200' of water left	
slate	1385	shale	2090	in hole	
sdly shale	1393	slate	2100	lime hrd	2820
red rock	1395	lime hrd	2105	shale	2825
sdly shale	1435	lime brkn & shale	2115	brkn lime	2850
lime medium	1445	Bad cave at 2100'		slate	2855
shale lgt	1475	slate blue	2135	shale blue	2875
sdly shale	1515	red rock	2150	slate drk	2885
lime brkn	1530	shale blue	2190	1 BW hr 2855'	
lime sdy	1535	lime hrd	2200	more water at 2885'	
shale	1545	shale grey	2205	Hole caving	
2 BW hr at 1535'		lime grey	2210	shale sdy blue	2900
red rock	1552	shale blue	2215	shale sdy blue	2955
lime	1560	sdly	2240	lime & shells	2958
shale blue	1585	slate blue	2255	shale grey top	
red rock	1590	lime hrd	2275	K.C.	2985
lime	1600	slate blue	2305	6 BW hr 2885-2895'	
shale lgt	1605	brkn lime	2325	lime mud	2995
lime sdy	1610	shale grey	2330	lime hrd	3000
slate drk	1628	lime hrd	2340	Bailing water	
lime hrd	1635	shale drk	2350	lime very hrd	3038
shale	1640	shale blue	2410	slate break	3040
red rock	1655	Bad cave at 2405'		lime hrd med.	3050
lime hrd	1665	shale	2415	lime brkn shale	3070
red rock	1675	lime	2422	lime grey	3080
lime lgt med.	1690	slate blue	2426	sdly lime	3092
red rock	1695	lime hrd	2432	HPW 3087-3092'	
red rock & shale blue	1700	lime brkn	2450	lime hrd	3153
red rock	1710	lime	2470	HPW 3123' shale	
lime brkn	1725	shale sdy	2510	shale	3157
Hole caving		Topeka lime	2518	lime hrd	3185
shale blue	1745	6 BW HR 2495-2510'		bailing water	
lime white	1760	U.R. 8" csg.		Hole caving	
shale blue	1780	lime hrd	2530	U.R. 6 5/8" to 3102'	
lime	1795	lime	2535	lime	3189
slate	1800	lime hrd	2542	bailing water	
shale	1815	lime mud	2562	lime hrd	3205

(OVER)

Sec. 29-21-9W

NE corner.

Wellman No. 1

Formation	Depth
U.R. 6 5/8" to 3180'	
shale drk	3210
Bailing water	
lime hrd	3250
2 BW per hr at 3215'	
hole caving	
shells hrd	3275
brkn shale	3290
lime	3307
UR 6 5/8" 3328' 5"	
sdyl shale	3373
shells lime sdy shale	3385
various colored shale	3397
shale	3400
Hole caving badly	
brkn lime	3420
chat	3430
some show of OIL	
sdyl lime	3435
Viola lime	3461
Small show oil 3450-56'	
lime	3475
brkn slate	3480
Set 5 3/16" at 3435'	
lime HFW 3510'	3515
Showing gas at 3492'	
sdyl lime	3525
lime	3540
slate & pyrites	3545
lime hrd	3550
U.R. pipe to 3481'	
siliceous lime	3553
Total Depth HFW	3553'