

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company THUNDERBIRD DRILLING, INC.  
Farm- Dickens No. 1

SEC. 32 T. 21 R. 9W  
SE NE NE

Total Depth. 3600'  
Comm. 3-10-60 Comp. 3-22-60  
Shot or Treated.  
Contractor. Thunderbird Drilling, Inc.  
Issued. 5-28-60

County Rice  
KANSAS



Elevation. 1702 DF

Production. 25 BOFD

CASING:  
8 5/8" 200' cem w/175 sx.  
5 1/2" 3599' cem. w/70 sx.

Figures Indicate Bottom of Formations.

sand & gravel	95
red bed	200
red bed, shale & shells	500
red bed & shale	795
anhydrite	835
shale & shells	1290
shale & lime	1630
lime	1790
lime & shale	2040
shale & shells	2410
shale	2450
lime	2515
lime & shale	3035
lime	3089
lime & shale	3390
sand	3400
lime & shale	3535
shale & sand	3550
shale & lime	3600RTD
Total Depth	

TOPS: SCOUT	
Heebner	2855
Brown Lime	2992
Lansing	3029
Kinderhook	3342
Misener	3375
Maquoketa	3397
Viola	3475
Simpson Sand	3544