

SECTION 10 TOWNSHIP 22S RANGE 14W

WELL NO. #1 P. Omlor.

COMPANY Sunray Mid-Continent Oil Co.

		NORTH				NE SE SE	
							0-
WEST							EAST
		SOUTH					

WELL NO.

COMPANY

CONTRACTOR

Smallwood Fld. Area Wildcat
NORTH

990 _____ FT. FROM S. LINE

_____ FT. FROM W. LINE

NE SE SE

	3800' Arbuckle Test	
11/4	MIRT	(DR#215)

11/6	Dr1g. 1060'
------	-------------

12/3	TD 38251	"	OVER	"
------	----------	---	------	---

FORM 504-5 SUNRAY

1957

12/4

TD 3825'. Pumping. No test.
Perfs 3550-3559'

12/5

TD 3825'. Pumping. No test.

12/6

TD 3825'. Pumped 84 B0 12 hrs.
Perfs 3550-3559'

12/9

TD 3825'. Pumping. Well not pumping
off. Perfs 3550-3559'

12/10

TD 3825'. P/64 B0 Day rate.
Perfs 3550-3559' Arbuckle Zone.
Complete (DR#239)

13
WILDCAT

S-513-A

CO. Starford ELEV. _____
SEC. 10 TWP. 22 RGE. 11W
COMPANY Sunray Mid-Cont. NO. 1

NOV 6 57

FIRST REPORT

FARM P. Orlor

LOC. NE SE SE

GEOL. _____
CONTR. Stickle Brg.
POOL Wildcat
SPUD 11/4/57

8" @ 323 w/325, WOG

NOV 8 1957

TO ~~Stafford~~ ELEV. 19360'

JO TWP 22 RGE 14

SUNRAY Mid-Cont. NO 1

COMPLETE

DEC 26 '57

FARM P. Omlor

LOC. N J. J.

HB 3292

Dg 3330

BL 3420

Lsg 3429

BKC 3664

C 3686

V10 3694

SSH 3744

A 3799

LTD 3822

GEOL.

CONTR. ~~Ind. Oil Dr'g.~~

Omlor

POOL

SPUD 11/1/57

3" 23 W 225, 2

HB 3294

Dg 3331 BL 3421 Lsg 3429

Ø 3506 DST 3540-63

60" 9/13" rec 600' fld 240'

clean gassy oil 360' MCO (80% oil

20% M no water) FP 65-270 BHP

1130 in 30" ~~BKC 3666~~ DST

3563-816" GB rec 30' H06 GCM

(80% oil) 300' SD 6 GCMW 780'

GC SW with scum oil FP 50-530

BHP 1030/30" porous zone

3591-3601 good staining and free

oil DST 3586-3603 60" WB

rec 35' VS OCM FP 15-25 BHP

210/30" BKC 3666 Cong 3687

Viola 3696 DST 3700-30 60"

WB 15" and died rec 32' M vs to oil

FP 10-25 IBHP 40 PBHP 40/30"

Simp Sh 3741 simp sd 3749

Arb 3800 DST 3801-04 60"

WB rec 30' M FP 10-25 BHP

1195/30" RTD 3825 ~~3825~~

ran log 5 1/2" 3677/100 log tops

WOST 2 Ran GRNL perf

23/3 594-99 scum oil, acidize

250 regular 500 jet-X & Ld

& 23 Bwph + scum oil decreased

to 18 Bwph 6 hrs. set plug.

3580 perf 48/ 3550-59 &

6 Boph 9 hrs NW T&R pop

pump today P

84 BO NW 12 hrs P 64 BO NT

P 4 Boph NW X State

test P 28.56 BO NW 8 hrs

P & 6 BO 0d NW

Lsg 3550-59

PB 3580 3.5° gravity

TD 3825