

10/8/62 RIGGING UP AND PREPARING TO DRILL.
RAN 5 JTS. 8-5/8" 20# NEW PIPE (209.80). SET @ 2:17 PM
WITH 200 SIB. PORTIX HAS. PLUGGED DOWN @ 3:15 PM.
CEMENT CIRCULATED.

10/9/62 DRILLING @ 775'.

0/10/62 DRILLING @ 1875'.

0/11/62 DRILLING @ 2990'.

0/12/62 DRILLING @ 2990'.

0/13/62 DRILLING @ 3257'.

0/14/62 DRILLING @ 3396'.

0/15/62 DRILLING @ 3555'.

0/16/62 RUNNING DST #1 3618-3622'

DST #1 3618-3622'. OPEN 35". WEAK BLOW FOR 5".

RECOVERED 6' ROTARY MUD. NB. IENP 11454/30".

FENP 10601/30", IFF-FFP 0, NI 1980/.

DST #2 3619-3626'. OPEN INR. 15 MIN. STRONG BLOW

DECREASING TO FAIR. GAS TO SURFACE IN 44". RECOVERED

3300' GASSY OIL. NO APPARENT WATER. IENP 11904/30",

FENP 11601/30", IFF 420, FFP 1135, NI 1990.

CURRENTLY DRILLING @ 3680'.

SCHLUMBERGER RAN GAMMA LATERAL INTEGRATED SONIC LOG

10/18/62 RAN 118 JTS OF 5 1/4" 14# CASINO (3702.19). SET @
3688 w/ 50 SIB. GOMBO PORTIX SALT SATURATED CEMENT.
PLUG DOWN @ 5:10 AM. RTD 3690'.

RECEIVED
STATE CORPORATION COMMISSION

JUN 18 1973

CONSERVATION DIVISION
Wichita, Kansas