

508 East Murdock

Wichita, Kansas


29-22-11W

Company - DEARDORF OIL CORPORATION
 Farm - Spangenberg No. 1

SEC. 29 T. 22 R. 11W
 SE SW NE

Total Depth. 3613
 Comm. 12-30-50 Comp. 2-19-51
 Shot or Treated.
 Contractor. Deardorf Oil Corp.
 Issued. 7-7-51

County. Stafford
 KANSAS



Elevation. 1829

Production. 185 bbls, no wtr

CASING:

10 3/4" 167' cem w/175 sx.
 5 1/2" 360' cem w/150 sx.

Figures Indicate Bottom of Formations.

sand, shells, red beds	395
shale, red beds	815
red beds	1030
sand, shale	1255
shale, shells	1380
shells, shale, salt	1545
salt, shale	1764
shale	1810
shale, sand	1870
lime	1985
lime sandy	2155
lime sandy, shale	2240
lime	2290
lime sandy	2332
lime, shale	2372
sand shaly, lime	2570
shale, sand	2745
lime sandy, shale	2814
lime, shale	2906
lime hard	2940
shale, lime	2979
lime hard, shells	2993
lime	3094
lime, shale	3172
shale, lime broken	3200
shale, red & gray	3250
lime, brown & shale	
grey	3260
lime white to grey	3270
lime grey dense	3290
lime grey fossil	3310
lime grey to wht dnse	3420
lime grey wht shaley	3470
lime gry dense blk,	
shaley	3500
lime gry inc. shale	
gray	3520
shale grey & red	3560
chert vari-colored	3570
(shale and sand)	
shale & sand	3580
shale green	3600
shale green sandy	3605
(show oil)	
dolomite	3613
Total Depth	

Tops:
 Dodge 3246
 Lansing 3263
 Conglomerate 3558
 Simpson 3576
 Arbuckle 3603

Sample circulated 1 1/2 hrs @ 3605
 RTD Dolomite. Good show oil.
 Top Arbuckle at 3603