

30 - 22 - 11W


Total Depth. 3666
Comm. 10-25-51 Comp. 11-8-51

County Stafford
KANSAS

Shot or Treated.

Contractor. Birmingham-Bartlett Drlg. Co.

Issued. 12-29-51



CASING:
8 5/8" 252' cem w/200 sxs.
5 1/2" 3664' cem w/125 sxs.

Elevation. 1852 RB
1849(m)

Production. 124 bbls & 25 wtr.

Figures Indicate Bottom of Formations.

surface sand, clay	85
shale, shells	350
red bed	590
anhydrite	600
shale, shells	1450
broken lime	1560
lime	1805
broken lime	1890
shale, shells	1910
shale, lime	2005
shale, shells	2880
lime, shale	3045
lime	3122
lime, shale	3284
lime	3515
lime, shale	3564
chert, lime	3569
lime	3575
Viola chert	3600
lime, chert	3610
shale	3660
dolomite	3663
arbuckle	3666 RTD
Total depth	

Tops:

Heebner	3123
Brown lime	3259
Lansing	3286
Viola	3563
Simpson shale	3606
Simpson sand	3629
Arbuckle	3663

DST #1 3429-46: weak blow; for
11 min. OPEN 30 min. Rec. 15' mud.
BHP 0

DST #2 3448-55: open 45 min.
rec. 60' muddy salt wtr. & 240'
salt wtr. BHP 1100#.

DST #3 3559-75: op. 30 min. Weak
blow 6 min. Rec. 5' mud. No BHP

DST #4 3630-36: Op 35 min.
Weak blow 5 min. Rec. 7' mud.
B P 155#

DST #5 3660-66: Op 30 min. rec.
120' OCM & 1128' oil. B P 1070#.
F. P. 350#