

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas


1-22-12 W

STANOLIND OIL & GAS CO.
Margaret Helmers No. 4.

SEC.1 T.22 R.12 W
~~SW SE NW~~
~~330-N 51 1650-B WL NW 1/4~~

Total Depth. 3567'
Comm. 4-21-42 Comp. 5-13-42
Shot or Treated.
Contractor.
Issued. 6-6-42

County. Stafford



Rotary O-3563 1/2 (CT)
Cable 3563 1/2 -67 (CT)

CASING:
8 5/8" 267' Cem.
4 1/2" 3558' 4" Cem.

Elevation.

Production. DD Pot. 583 B.
IC 686 B.

Figures Indicate Bottom of Formations.

cellar	5
sand	95
shale & shells	210
sand	235
shale	275
red beds & shells	578
anhydrite	600
shale & shells	1080
salt & shale	1182
shale & shells	1454
shale & lime	2145
shale	2155
lime & shale	2495
lime	2518
shale	2535
shale & lime	2750
shale	2770
lime	2982
lime & shale	3202
shale	3230
lime	3268
lime & shale	3317
lime	3479
chert (Viola)	3507
shale (Simpson)	3557 1/2
Arbuckle dolomite	3567
Total Depth.	

Lansing lime 3230-3479 (SIM)
Arbuckle dolomite 3557 1/2 -3567
(Casing Tally)

Initial swab test off btm
2 1/2 BOPH no wtr
D.D. Potential 583 Bbls -
I.C. 686 Ebls.