

1-22-12W

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company. J. D. FERRELL OIL CO., INC. & PETROLEUM, INC. SEC.
Farm. Wellies "A" No. 3

1 T. 22 R. 12W
CE₂ NE NE

Total Depth. 3585'

Comm. 4-1-49

Comp. 4-16-49


County. Stafford

KANSAS

Shot or Treated.

Contractor. J. D. Ferrell Drilg. Co., Inc.

Issued. 6-18-49



CASING:
8-5/8" 251' Cem. W/175 Sx.
5-1/2" 3578' Cem. W/100 Sx.

Elevation. 1792' Ind

Production. 35 bbls.

Figures Indicate Bottom of Formations.

cellar	5
sand	60
shale & sand	120
shale & shells	252
red bed & shale	320
shale & shells	570
anhydrite	615
shale & shells	1040
shale, salt, shells	1330
shale & lime	1450
lime	1480
lime brkn	1585
lime & shale	1675
lime	1810
shale & lime	1955
lime brkn	2105
lime & shale	2260
shale & shells	2365
shale	2555
shale & shells	2855
shale & lime	2870
lime	3010
lime & shale	3090
lime	3495
lime & shert	3515
chert	3539
shale, sand, shells	3565
shale & lime RTD	3580
shale & lime ?	3585
Total Depth	

Tops:

Heebner	3059
Br. Lime	3189
Kansas City	3214
Viola	3492
Simpson Shale	3533
Arbuckle	3578