

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas


4-22-12W

Company. WESTERN PETROLEUM CO.
 Farm. Sittner "A" No. 1

SEC. 4 T. 22 R. 12W
 SW SE NW

Total Depth. 3641'
 Comm. 8-31-61 Comp. 9-9-61
 Shot or Treated.
 Contractor. Western Petroleum Co.
 Issued. 1-20-62

County Stafford
 KANSAS



CASING:
 8 5/8" 233' cem w/260 sx.
 5 1/2" 3638' cem w/100 sx.

Elevation. 1862' DE

Production. 179 BOPD

Figures indicate Bottom of Formations.

clay, sand	90
sand, gravel	210
red bed	550
Anhydrite	660
shale, shells	1020
shale & shells	1528
lime & shale	2342
shale & lime	2750
lime & shale	3345
lime	3500
lime & chert	3571
chert & shale	3500
shale, lime	3641 RTD
Total Depth	

TOPS:

Anhydrite	660
Heebner	3145
Iatan	3279
Lansing	3294
Viola	3541
Simpson	3581
Arbuckle	3635

DST #1 3305-45', op 1½ hrs, good blow declining to a fair blow. GTS in 18 min, TSTM. Rec. 190' slight O&GCM, IBHP 1105#/30 min FBHP 870#/30 min, IFP 65#, FFP 90#.

DST #2 3410-3432', op 1½ hrs, strong blow GTS in 6 min, 20 min gauged 886,000 CF (Stable thruout balance of test) Rec. 60' of GCM. No oil. IBHP 1280#/30 min, FBHP 1280#/30 mins. IFP 135#, FFP 160#.

DST #3 3477-93', op 1½ hrs, strong blow. thruout. GTS 12 min, TSTM. Rec. 20' HO & GCM, 180' HGCFMO. No apparent wtr., IBHP 1220#/30 min, FBHP 1170#/30 mins, IFP 30#, FFP 55#.

DST #4 3636-41', op 1 hr, good blow to fair blow at end of test. Rec. 2300' visible gas, 380' clean oil, 100' froggy oil. IBHP 1220#/30 min, FBHP 1220#/30 mins, IFP 105#, FFP 130#, HH 1990#.