

4-22-12W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
50S East Murdock, Wichita, Kansas

Company- WESTERN PETROLEUM CO., INC.
Farm- Sittner "A" No. 2

SEC. 4 T. 22 R. 12W
NE SW NW

Total Depth. 3860'
Comm. 12-4-61 Comp. 12-15-61
Shot or Treated.
Contractor. Western Petroleum Co., Inc.
Issued. 3-31-62

County Stafford
KANSAS



Elevation. 1865' DF

Production. S.W.D.W.

CASING:

8 5/8" 265' cem w/260 sx.
5 1/2" 3710' cem w/100 sx.

Figures Indicate Bottom of Formations.

sand clay	40
sand gravel	210
shale	268
red bed	662
Anhydrite	850
shale & shells	1540
shale & lime	1748
lime & shale	2290
shale & lime	2565
lime & shale	3043
lime	3145
lime & shale	3310
lime	3510
lime & chert	3565
chert lime	3606
lime & shale	3765
cherty lime & shale	3840
lime	3860 RTD
Total Depth	

TOPS:

Anhydrite	665
Heebner	3154
Iatan	3290
Lansing	3304
Base Kansas City	3522
Conglomerate	3548
Viola	3562
Simpson	3602
Arbuckle	3670

DST #1 3426-45', op 57 mins, weak blow
17 mins, Rec. 62' rotary mud, few oil
specks. IBHP 1080#/30 mins, FBHP 480#/30 mins,
IFP-FPP 0#.

DST #2 3485-3510', op 51 mins, weak blow
26 mins, rec. 65' rotary mud w/few oil
specks. IBHP 510#/30 mins, FBHP 0#/30 mins.
IFP-FPP 0#.