

12-22-12W

Company - STANOLIND OIL & GAS CO.
 Farm - O. Wokaty No. 2

SEC. 12 T. 22 R. 12W
 NE SW NW
 990' N of SL, 990' E of WL, NW

Total Depth. 3591

Comm. 7-2-51

Comp. 8-1-51


Shot or Treated.

Contractor.

Issued. 9-22-51

County. Stafford

KANSAS



CASING:
 8 5/8" 606' cem. w/400 sx
 5 1/2" 3582' cem. w/150 sx

Elevation. 1831 RDB
 1828(m)

Production. 4640 BO

Figures Indicate Bottom of Formations.

sand, shale	130
red bed, shale	380
red bed, shells	597
anhydrite	605
red bed, shale, shells	1150
salt, shells	1320
shale, shells	1475
shale, lime	1620
lime	1725
shale, lime	2415
shale, shells	2600
shale, lime	2920
lime	3091
lime, shale	3249
lime	3503
lime	3529
lime	3535
shale	3575
sandy gr. shale show of	
live oil & gas	3587
brown, sugary dolomite	
lime bleeding oil & gas	3591
Total Depth	

Tops:

Heebner	3091
Lansing	3249
Viola	3503
Simpson	3529
Arbuckle	3582

Ran Schlumberger Electric Log
 to T.D.

Total Depth:

By Schlumberger: 3587

By Rotary Drill: 3587

Acidized w/500 gal. Dowell Acid

Test:

Six hour swabbing, 6.54 BOPH,
 no water

Landed 2 1/2" tubing @ 3569

Oil or Gas Sands or Zones

Lansing 3249-3503'

Arbuckle 3582-3591'