

12-22-12W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- BIRMINGHAM-BARTLETT DRILLING CO.
Farm- Willinger No. 3

SEC. 12 T. 22 R. 12W
SE SW NE

Total Depth. 3599
Comm. 6-10-53 Comp. 6-23-53
Shot or Treated.
Contractor. Birmingham-Bartlett Drllg Co.
Issued. 9-12-53

County Stafford
KANSAS



CASING:

8 5/8" 207' cem w/180 sx
5 1/2" 3594' cem w/125 sx

Elevation. 1803 R.B.

Production. 30 BOPD / 25% wtr

Figures indicate Bottom of Formations.

shale	207
shale, red bed	570
anhydrite	600
shale, shells	1500
lime, shale	1570
lime broken	2000
lime brkn, shale	2115
shale, shells	2305
lime brkn, shale	2600
lime, shale	2900
lime	3055
lime, shale	3130
shale	3197
lime brown	3205
lime, shale	3255
lime	3500
chert	3539
lime	3590
arbuckle	3594 RTD
arbuckle	3599
Total Depth	

Tops:	
Heebner	3066
Brown Lime	3196
Lansing	3221
Base Kansas City	3473
Viola	3489
Simpson	3541
Arbuckle	3591 1/2

Drllg-in info:
Deepened 5' to 3599'
After acidizing and squeeze
job, well swabbed 2 1/2 BOPH for
8 hrs. P.O.P.
Potential taken on 8-10-53
30 BOPD / 25% water