


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. PETROLEUM, INC.
Farm. Hitz No. 1

SEC. 2 T. 22 R. 12W
SE NE NW

Total Depth. 3598
Comm. 10-15-52 Comp. 10-26-52
Shot or Treated.
Contractor Garvey Drilling Co.
Issued. 1-3-53

County Stafford
KANSAS



Elevation. 1829

Production. 34 bbls 81% water

Figures indicate Bottom of Formations.

sand	130		
shale	155	TOPS	
sand	195	Heebner	3086
shale w shells	225	Brown lime	3217
red shale	615	Lansing	3239
anhydrite	628	Simpson	3537
shale w shells	1075	Arbuckle	3590
lime & shale	1765		
lime	2070		
lime w shale	2800		
lime	3085		
lime & shale	3175		
lime	3580		
shale	3590		
lime	3598	T. D.	

DST #1 3292-3315 open 1 hr. rec. 30' oil cut mud, 600' froggy oil, 300' free oil, 810# BHP.

DST #2 3358-3382 open 1 hr. rec. 53' heavily oil cut mud, 478' froggy oil, 2' salt water BHP 1070#

DST #3 3386-3420 open 1 hr. rec. 70' slightly oil cut mud, 100' muddy oil, 10' water BHP 1260#

DST #4 3426-3440 open 40 minutes, rec. 2040' oil BHP 1400#

DST #5 3591-3594 open 1 hr. rec 120' gas, 30' slightly oil & gas cut mud. 0# BHP.