


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - PETROLEUM, INC.
Farm - Krug No. 1

SEC. 2 T. 22 R. 12W
N/2 SW SW

Total Depth. 3654
Comm. 2-15-49 Comp. 2-27-49
Shot or Treated.
Contractor. J. A. Melland
Issued. 5-28-49

County. Stafford
KANSAS



Elevation. _____

Production. Dry

CASING:

8 5/8" OD 250' cem w/150 sx.
5" OD 3634' cem w/50 sx.

Figures Indicate Bottom of Formations.

surface sand, shale	60
sand	130
shale, red bed	790
shale, shells	1130
salt	1310
shale, lime	1475
lime	1585
lime, sand, hrd	1885
lime	2160
lime, shale	2945
lime	3130
lime, shale	3280
lime	3549
chert	3563
lime cherty	3580
shale, lime	3605
lime RTD	3649
lime	3654
Total depth	

Tops:

Heebner	3124
Dodge	3142
Arbuckle	3633

Rotary drilling completed 2-27-49,
Ran DST at 3649', open 45 mins, rec.
120' gas cut mud and oil and 230' of
oil, no water.
Set and cemented 5" OD casing at 3634'
w/50 sx. cement. Plug pumped down at
5:45 PM, 2-28-49. Casing cem by Halliburton
Process, using Halliburton bulk cement.
Slope tests were taken at 500' intervals,
and no deflections from vertical were recorded.