


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
 508 E. Murdock, Wichita, Kansas

Company - A. S. RITCHIE ETAL
 Farm - Krankenberg No. 1

SEC. 3 T. 22 R. 12W
 NE NW SE

Total Depth. 3604½ DF
 Comm. 4-24-50 Comp. 6-12-50
 Shot or Treated. 1000 gals acid.
 Contractor. Derby Drlg.
 Issued. 10-7-50

County. Stafford
 KANSAS



Elevation. 1846 DF

Production. 61 bbls.

CASING:

8 5/8" 251' cem w/170 sx.
 5½" 3602' cem w/75 sx.

Figures Indicate Bottom of Formations.

sand	110
shale, shells	251
red rock	345
shale, shells	626
anhyd.	653
shale, shells	825
shale, salt	1310
lime, shale	1635
shale, shells, sand	1770
lime	1850
sand	1880
lime	2245
shale, shells	2335
shale	2535
lime, shale	2690
lime	2790
shale	2835
lime	3125
lime, shale	3219
shale	3253
lime	3532
chert	3561
lime	3605
Total depth 3605 =	3603
Rotary total depth 3603 DF	
lime	3603 - 3604½
Total depth D.F.	

Tops: D.F.

Anhydrite (drillers)	621
Brown lime	3250
Lansing K. C.	3272
Viola chert	3519
Reworked Simpson shale	3546
Arbuckle dolomite	3602

Samples begin at 3200' in the Douglas shale