


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- LEBEN DRIG. CO. INC.
Farm- Stargel No. 1

SEC. 4 T. 22 R. 12W
SW SW NE

Total Depth. 3654'
Comm. 8-23-56 Comp. 9-4-56
Shot or Treated.
Contractor.
Issued. 10-13-56

County Stafford
KANSAS



Elevation. 1865' KB.

CASING:
8 5/8" 277' w/225 sx cem.

Production. Dry

Figures indicate Bottom of Formations.

surface clay-sand	163
sand-shale	277
shale-shells-sand	400
red bed	520
shale-red bed	656
Anhydrite	682
shale-shells	795
shale-red bed	977
shale-shells	1252
lime-shale	1889
sdv lime	1912
shale-lime	2518
shale	2653
shale-lime	3102
lime	3182
shale	3292
lime	3509
lime-shale	3569
cherty lime	3589
lime-shale	3646
Arbuckle	3649
lime	3654
Total Depth RTD*	

TOPS:	
Heebner	3148
Toronto	3168
Douglas	3181
Brwn lime	3283
Lansing-Kansas City	3295
Conglomerate	3541
Viola	3547
Simpson	3539
Arbuckle	3645

DST #1 - 3646-49 - Tool open 1 hr.,
Shut in 20 min. Fair blow throughout,
rec. 300' gas & 50' OC w/1' free oil in tool. ISIP 170#, no other pressures.

DST #2 - 3647-54 - Tool open 1 1/2 hrs.
S.I. 20 min., Good blow throughout,
red. 600' gas, 30' OC wtr. & 200' salt wtr., FSIP 310#, ISIP 1240 #,
120# FFP & 60# IFP.