

59156

STANOLIND OIL & GAS CO.
Henry Krankenberg No. 1.

SEC. 6 T. 22 R. 12 W
SE NE SW
1650' N SL 2310' E WL SW $\frac{1}{4}$

DISCOVERY WELL

County. Stafford

Total Depth. 3660'

Comm. 7-2-43

Comp. 7-18-43

Shot or Treated.

Contractor.


Issued. 9-4-43

Rotary O-3660

CASING:

8 $\frac{5}{8}$ " 250' 11" Cem.
4 $\frac{1}{2}$ " 3654' 8" Cem.

Elevation.



Figures Indicate Bottom of Formations.

Production. Temp. Pot. 80 B.

surface soil & clay	0-44
sand, clay, gravel	280
red bed & gravel	415
red bed & shale	800
anhydrite	815
shale & shells	1420
shale	1575
lime	1770
lime & shale	2510
lime brkn & shale	2570
shale & sand	2632
lime	2679
lime brkn	2780
lime	2833
lime & shale	2985
lime	3025
shale & lime	3035
lime	3055
lime & shale	3310
lime	3559
lime cherty	3625
lime & shale	3641
shale	3656
Arbuckle dolomite	3660
Total Depth.	

Tops: Lansing	3320
Arbuckle	3656