


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - THE ATLANTIC REFINING CO.
Farm - Alpers No. 7

SEC. 7 T. 22 R. 12W
SE SE SW
330' N of SL,
288' W of EL
County. Stafford
KANSAS



Total Depth. 3676' R.B.
Comm. 8-21-48 Comp. 9-22-48
Shot or Treated. Acidized w/1000 gals.
Contractor. Campbell Drig. Co.
Issued. 11-6-48

CASING:

8 5/8" 291' cem w/175 sx.
5 1/2" 3674' cem w/150 sx.

Elevation. _____

Production. Pot. 145 BOPD.

Figures Indicate Bottom of Formations.

shale and sand	205
shale and lime shells	290
redbed and shale	710
shale and shells	1115
shale, shells, salt	1535
shale and lime shells	1635
shale and lime	2100
lime	2260
shale and lime	2345
shale and lime shls	2515
shale and lime	2685
shale and shells	2765
shale and lime	2810
lime	2955
lime brkn	3025
lime	3295
shale and lime	3330
lime	3619
conglomerate	3645
shale	3669
lime	3676 R.B.
total depth R.B.	

Tops:

Arbuckle 3673' R.B.

Moved in cable tools, Drilled
plug. Bailed hole. SLM TD 3676 1/2'
Fillup 4 Bbls. oil pr hr.
Dumped 2 bbls. acid down casing.
Tested 7 1/2 BOPH.
Acidized w/1000 gals.
Swabbed 40 BOPH, trace
of acid water.
Ran tubing and rods.
State Test: 10-15-48,
8 hrs. 48.18 BO, 50% wtr.
Pot. 145 Bbls./Day.
PRODUCING AREA: 3674-3676