


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

SINCLAIR PRAIRIE OIL CO.
Cora Crawford No. 2.

SEC. 7 T. 22 R. 12 W
CNW NE
660'f N 510'f WL NW $\frac{1}{4}$ NE $\frac{1}{4}$

Total Depth. 3670'
Comm. 9-29-43 Comp. 10-16-43
Shot or Treated. 1000 Gals. Acid
Contractor. Harbar Drlg. Co.
Issued. 12-4-43

County. Stafford



CASING:
9" 289'
5 $\frac{1}{2}$ " 3666' RFM

Elevation.

Production. Pot. 2234 B.D.D.,
No wtr
Figures Indicate Bottom of Formations.

sand	40
sand & shells	315
sand & shells	385
red bed	700
lime & shale	1000
shale & shells	1430
salt	1540
shale & shells	1635
lime & shale	1720
shale & shells	1820
lime shells	1860
lime brkn	2415
lime	2750
lime & shale	2890
lime brkn	2960
lime & shale	3353
lime	3490
lime & shale	3580
chert	3595
chert-conglomerate	3630
lime & chert	3655
shale	3670
Total Depth.	

Top Arbuckle Lime 3666 RFM
(3663 Meas. fm sur. lev)

Cored 3650-56

rec. 1' green shale

Cored 3656-61 rec. 3 $\frac{1}{2}$ '

top 1 $\frac{1}{2}$ ' green sdy shale

btm 2' green shale