


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company. SINCLAIR PRAIRIE OIL CO.
Farm. Cora Crawford No. 4.

SEC. 7 T. 22 R. 12 W
SW NE NE
990' fN & E Lines NE $\frac{1}{2}$

Total Depth. 3673'
Comm. 8-29-44 Comp. 9-18-44
Shot or Treated.
Contractor. Harbar Drlg. Co.
Issued. 1-6-45

County. Stafford
KANSAS



CASING:
9 5/8" 286' Cem.
5 1/2" 3672' DFM Cem.

Elevation. _____

Production. Pot. 1265 B., No wtr

Figures Indicate Bottom of Formations.

surface clay	286	Potential 1265 bbls oil,
red bed	601	no wtr after 1500 gals.
anhydrite	740	acid, some gas
red rock & shale	980	
shale & shells	1300	
salt	1310	
shale & salt	1490	
shale & lime	1530	
lime	1870	
lime & shale	1880	
lime	2190	
shale	2216	
shale & lime	2360	
shells & shale	2620	
lime & shale	2670	
lime	2710	
lime & shale	2770	
lime	3180	
lime & shale	3335	
lime	3415	
lime hrd	3448	
lime	3565	
lime cherty	3618	
lime	3633	
conglomerate	3660	
shale green, shells	3672	
Arbuckle lime	3673	
Total Depth		

Tops:
Lansing-K C 3335
Conglomerate 3560
Viola 3567
Simpson 3617
Arbuckle 3672 DFM