


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

PHILLIPS PETRO.CO.
F. Hitz No. 2.

SEC. 7 T. 22 R. 12 W
CSW NW
660'f SL 660'f WL NW $\frac{1}{4}$

County. Stafford



Total Depth. 3669'
Comm. 5-26-43 Comp. 6-23-43
Shot or Treated. 300 Gals. Acid
Contractor. Rine Drlg. Co.
Issued. 10-16-43

CASING:
8 5/8" 428'
5 1/2" 3661'

Elevation.

Production. Pot. 3000 B.

Figures Indicate Bottom of Formations.

sand	263
sand, red rock	298
red rock	703
shale & shells	1198
shale & lime shells ?	1498
lime & shale	1955
lime	2053
shale & lime	2233
shale & shells	2418
lime	2423
lime & shale	2939
lime	2993
lime & shale	3068
lime	3073
shale	3108
lime	3203
lime & shale	3328
lime	3474
lime & shale	3553
lime & chert	3587
chert & shale	3633
shale	3661
lime	3669
Total Depth.	

Tops: Lansing- K.C.	3331
Simpson	3605
Arbuckle	3661