

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

Wichita, Kansas

Company- STANOLIND OIL AND GAS CO.
Farm- L. Ahnert No. 3

SEC. 10- T. 22 R. 12W
NE NE NE
330' S of NL, 330'
W of EL of NE $\frac{1}{4}$
County Stafford
KANSAS

Total Depth. 3681
Comm. 6-4-50 Comp. 6-20-50
Shot or Treated.
Contractor.
Issued. 12-29-51

CASING:

8 5/8" 644' cem w/450 sxs.

Elevation. 1848 RDB

Production. dry

Figures Indicate Bottom of Formations.

sand, shells	400
red bed	634
anhydrite	665
shells, shale	1500
lime, shale	1645
shale, sand	1790
sand, lime	1955
lime	2075
sandy lime, shale	2215
shale, lime	2860
lime	3060
shale, lime	3075
lime	3135
lime, broken	3195
shale, lime	3293
lime	3524
lime; shale	3556
lime, chert	3601
simpson lime	3620
shale	3662
lime	3681
Total depth	

Tops:

Lansing	3293
Conglomerate	3556
Simpson	3601
Arbuckle	3662

Lane Wells electric log to
T. D. 3681
Cored No. 1 2' 3663-3665
Rec. 2' shy. dolo. SS0
DST T. D. 3666
Packer set at 3664
Tool open 2 hrs.
Rec. 15' drlg. mud BHP zone
Cored No. 2 5' 3666-3671
rec. 3' dolo. fair por.
SS0
DST T. D. 3671
packer set at 3666
Tool open 1 hr.
rec. 35' mud BHP-zero
Cored N. 3 5' 3671-3676
Rec. 18" shy. dolo. 6" dolo.
fair por. & SO
DST t. D. 3676
Packer set at 3671 Tool open
2 hrs. Rec. 35' drlg. mud.
Cored No. 4 5' 3676-3681
Rec. 2' dolo. SS0
Top 1' fair por. Bottom 1'
dense no show
DST T. D. 3681 packer set at
3676 Tool open 1 hr. rec. 60'
muddy formation wtr.