

WELL LOG BUREAU-- KANSAS GEOLOGICAL SOCIETY

508 E. Murdock, Wichita, Kansas

Company - STANOLIND OIL AND GAS CO.

Farm - K. Teichman

No. 2

SEC. 10 T. 22

R. 12W

CW $\frac{1}{2}$ NW SE1980' NSL, 2310' WEL of SE $\frac{1}{4}$

Total Depth. 3656

Comm. 2-23-50

Comp.

3-9-50

County. S.afford

KANSAS

Shot or Treated.

Contractor.

Issued. 9-23-50



CASING:

8 5/8" 645' cem w/400 sx.

5 1/2" 3651' cem w/100 sx.

Elevation. 1855 RDB

Production. 225 bbls.

Figures Indicate Bottom of Formations.

sand redbed	633
anhydrite	706
shale	1463
lime, shale	1674
lime Ft. Riley	1865
lime, shale	2208
shale	2914
lime, shale	3070
lime Topeka	3125
lime	3139
lime	3269
lime	3350
lime, shale	3405
lime KC	3431
lime	3454
lime, shale	3473
lime	3543
lime	3547
lime sdy, chert	3582
lime sdy, chert	3595
shale	3636
shale grn waxy	3639
shale sdy gry grn waxy	3648
shale grn sdy, mixroxlyn	
dolomite w/pyrite strks.	3651
dolomite scattered	
porosity	3656
Total depth	

Tops:

Heebner	3139
Iatan	3269
Lansing	3292
Viola	3543
Simpson	3582
Arbuckle	3651

Water sands:

Anhydrite 633