

WELL LOG BUREAU-- KANSAS GEOLOGICAL SOCIETY

508 E. Murdock,

Wichita, Kansas

Company - CITIES SERVICE OIL CO.

Farm - Voigt

No. 1

SEC. 11 T. 22 R. 12W

SE SW NE

330' N. & 990' E. of cen.

Total Depth. 3634

Comm. 2-26-50

Comp. 3-13-50

Shot or Treated. Acid 500 gals. 3-14-50 1000 gals. 3-18-50

Contractor. Holm-Louis Drlg. Co.

Issued. 5-27-50

County. Stafford

KANSAS



CASING:

8 5/8" 240' cem. w/200 sx.

5 1/2" 3627' cem. w/150 sx.

Elevation. _____

Production. Phys. bot. 143 oil,

63 wtr. 24 hrs.

Figures Indicate Bottom of Formations.

clay	75
sand	105
shale & shells	160
sand & shale	252
shale & redbed	615
anhyd.	635
red bed & shale	1410
shale & shells	1700
lime & shale	1830
lime	1895
lime & shale	2170
shale & shells	2345
lime & shale	2655
shale & lime	2785
lime & shale	2850
lime	3105
lime & shale	3280
lime	3353
lime & shale	3360
lime	3556
chert	3572
lime	3629
3629 RTD = 3629 SLM	
lime	3634
Total Depth	

Tops:

Lansing	3273
Cherty congl.	3544
Viola	3552
Simpson shale	3573
Arbuckle	3626

Pen. 8'

8 gals. oil per hr.