

KANSAS WELL LOG BUREAU---KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY PETROLEUM, INC.

SEC. 15 T. 22 R. 12W

FARM Freuhauf

NO. 1

LOC. NE SW SW

TOTAL DEPTH 3700

COMM. 9-27-50

COMP. 10-9-50


SHOT OR TREATED

CONTRACTOR Garvey Oil

ISSUED 12-9-50

COUNTY Stafford

KANSAS



ELEVATION 1859 DF

PRODUCTION 284 bbls / 4 % wtr.

CASING

8 5/8" 218'

5 1/2" 3699'

FIGURES INDICATE BOTTOM OF FORMATIONS

shale 60

sand 110

shale, shells 140

sand, shale 645

shale, shells 958

anhydrite 979

shale, shells 1225

salt, shale 1370

lime, shale 1820

br. lime 2010

lime, shale 2150

lime 3128

lime, shale 3210

shale 3275

lime 3295

chert viola 3600

shale 3625

lime 3695

lime 3700

Total Depth

Tops:

Heebner 3144

Toronto 3162

Base Oread 3179

Br. Lime 3275

Lansing 3297

Viola 3557

Simpson 3602

Arbuckle 3672

DST #1, 3322-45, open 1

hr, closed 15 mins., rec.

60' heavily oil and gas

cut mud.

DST #2, 3347-80, open 30

mins., closed 14 mins., rec.

10' mud w/slight rainbow.

DST #3, 3425-60, open 1

hr, closed 15 mins., rec.

55' gas cut mud.

DST #4, 3458-98, open 1

hr, closed 15 mins., rec.

50' very slightly oil &

gas cut mud.