

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY  
508 E. Murdock,  
Wichita, Kansas

Company - BIRMINGHAM-BARTLETT DRUG CO.  
Farm - Schade  
No. 2

SEC. 16 T. 22 R. 12W  
NE NE NE

County. Stafford  
KANSAS

Total Depth. 3685  
Comm. 3-31-50 Comp. 4-11-50  
Shot or Treated.  
Contractor. Birmingham-Bartlett  
Issued. 8-25-51



CASING:  
8 5/8" 220' cem. w/150 sx.

Elevation. 1867

Production. Dry

Figures Indicate Bottom of Formations.

|                  |      |
|------------------|------|
| sand             | 150  |
| shale & shells   | 220  |
| red bed & shells | 580  |
| red rock         | 650  |
| anhyd.           | 675  |
| shale & shells   | 1575 |
| lime brkn        | 2085 |
| shale & lime     | 2100 |
| shale & shells   | 2500 |
| shale & lime     | 2910 |
| lime             | 2970 |
| lime & shale     | 3085 |
| lime             | 3250 |
| shale            | 3292 |
| Brown lime       | 3307 |
| lime             | 3570 |
| Viola chert      | 3603 |
| lime, chert      | 3650 |
| shale            | 3675 |
| lime             | 3685 |
| Total Depth      |      |

|             |      |
|-------------|------|
| Tops: Scout | 3160 |
| Heebner     | 3291 |
| Brown lime  | 3311 |
| Lansing     | 3552 |
| Congl.      | 3566 |
| Viola       | 3620 |
| Simpson     | 3683 |
| Arbuckle    |      |

DST 3603-85 open 1/2 hr. rec.  
50' wtr.