

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas


Company- R. W. SHIELDS
Farm- Stargel

No. 1

SEC. 17 T. 22 R. 12W
NE NE SE

Total Depth. 3695'
Comm. 4-4-59 Comp. 4-14-59
Shot or Treated.
Contractor. Glenn W. Peel Drlg.
Issued. 7-13-59

County Stafford
KANSAS



Elevation. 1871' KB

Production. 50 BOPD

CASING:

8 5/8" 252' cem.
5 1/2" 3694½' cem w/125 sx.

Figures Indicate Bottom of Formations.

sand	125
shale	465
red bed	1125
shale & shells	1430
Anhydrite	1455
shale and lime	1570
lime w/shale strks	1710
salt & shale	1825
lime	2020
lime and shale	2115
lime	2245
shale and lime	2535
shale	2875
lime	3205
shale & lime	3325
lime	3695
Total Depth	

TOPS: KB

Heebner	3157
Brown Line	3294
Lansing	3314
Viola	3582
Simpson	3634
Arbuckle	3691

DST #1 3338-58', op 1 hr., strong blow
thruout test, shut in 20 mins., rec. 60'
gas, 90' gas cut mud, 300' salt water.
BHP 1180#, FP 50-205#.

DST #2 3434-58', op 1 hr, good blow thruout
test. Shut in 20 mins., rec. 225' gas,
45' muddy salt water. BHP 565#, PF 25-50#.

DST #3 3482-3516', op 1 hr, 10 mins., weak
blow thruout test. Shut in 20 mins. Rec.
30' oil specked mud. BHP 105#, FP 12-25#.

DST #4 3692-95', op 1½ hrs, good blow
thruout test. Shut in 20 mins. Rec. 420'
gas, 150' oil, 60' oil cut mud. BHP 1105#.
FP 50-105#.