


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

STANOLIND O.G.CO.
William Harms No. 1.

SEC.18 T.22 R.12 W
NE NW NE NW
2310' N SL 1835' E WL NW $\frac{1}{4}$

Total Depth. 3670'
Comm. 4-1-42 Comp. 4-19-42
Shot or Treated.
Contractor.
Issued. 6-13-42

County. Stafford



CASING:
8 5/8" 256' 5" Cem.
5 1/2" 3665' 2" Cem.

Elevation.

Production. DDIC Pot. 3152 B.

Figures Indicate Bottom of Formations.

No wtr

cellar	6
sand	685
anhydrite	720
shale & red beds	1070
shale	1550
sand & shale	1627
shale & lime	1757
lime	2060
lime & shale	2243
lime	2290
shale & lime	2853
lime	2935
lime & shale	3040
lime	3060
shale & lime	3115
lime	3212
lime & shale	3279
lime	3428
shale & lime	3466
lime	3578
chert	3603
chert & shale	3618
shale	3665
Arbuckle dolomite	3670
Total Depth.	

Lansing lime 3320-3602
Arbuckle dolomite 3665-3670

Rotary O-3670
Cable tools were used to
drill out cement plug to
3670(CT)
Tested 7 gallons oil per hr
when plug was drilled
D.D.I.C. 3152 BOPD, no wtr