

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg. Wichita, Kansas

Company: BARNSDILL OIL COMPANY
Farm: Durham No. 1

SEC. 22 T. 22 12W
SE NE NE

Total Depth. 3699'

Comm. 1-21-48


Comp. 2-4-48

County. Stafford
KANSAS

Shot or Treated.

Contractor.

issued 5-8-48



CASING:

8-5/8" OD 215.08'
5-1/2" OD 3706.42'

Elevation. _____

Production. 14 BOPD

Figures indicate Bottom of Formations.

sand, shale & shells	0-215
shale, shells & red bed	520
red bed & shale	675
anhydrite	702
shale & shells	1550
shale & lime	1880
lime	2040
lime & shale	2510
shale	2560
shale & shells	2665
shale & lime	2965
lime	3570
lime & cherty Viola	3630
lime	3699
Total Depth	

Tops:

Heebner	3169
Brown Lime	3299
Lansing K.C.	3313
Viola	3581
Simpson	3639
Arbuckle	3693

1. 3352 to 3359; samples circulated at 3361 had light odor and spotted saturation in fair porosity.
2. 3389 to 3397; poor porosity, light staining.
3. 3453 to 3459; samples circulated at 3461 had faint odor, spotted saturation in good oolistic porosity. In order to test this zone a Drill Stem Test was made at 3461 with Packer set at 3451. The tool was left open a total of 30 minutes and recovered 30' of drilling mud.
4. 3490 to 3501; fair porosity, spotted black oil staining.
5. 3515 to 3521; good porosity, light spotted staining.

All measurements from the top of rotary bushing.