

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY

UNION NATIONAL BANK BLDG WICHITA KANSAS.

Location SE cor SE.

Sec. 36 T. 22 R. 12W

Casing Record

County- Stafford.

20" 151 10" 2836
 15 1/2" 548 8 1/2" 3253
 12 1/2" 1481 65/8" 3478
 Total Depth 3599'.

Farm- Richardson

No. ~~22~~ #1

Company- Midwest Exploration Co.

Contr.- Chew

Comm.- 4/10/30.

Comp.- 9/9/30.

Shot

Quarts Between

Correspondence Regarding This Well Should Be Referred to



Elevation

Figures Indicate Bottom of Formations.

Date Issued. 11/8/1930.

Initial Production 210 bbls-

1320 bbls after deepening.

Swabbed 57 bbls per hr.

Formation	Depth	Formation	Depth	Formation	Depth
cellar	20	sdv shale blue	2165	lime brkn	3305
sand & gravel	30	sand 4 BW HW	2175	4,165,000 show gas	
sand	140	sand 10" at 2175'	2205	3305-3311'	
red rock	480	lime	2245	lime brkn	3325
red rock	541	shale blue	2360	sdv lime brkn	3355
talc	545	10" U.R. to 2238'		lime	3385
lime	548	lime	2370	6" at 3385'	
shale red & blue	570	shale blue	2383	lime brkn	3390
shale blue	600	lime	2387	Straight reaming for 6"	
red rock	670	shale blue	2430	1300' water & 500' oil	
shale blue & brown &		sand 1 BW	2435	lime show gas	3392
lime shells	725	lime	2440	lime	3414
red rock	750	sdv shale blue	2460	lime & shale	
shale blue & red		lime	2500	breaks	3475
rock	860	shale blue & shells	2540	lime	3482
shale blue	925	lime	2550	6" U.R. to 3473'	
shale brown	950	lime & shale blue	2575	shale brown	3495
shale blue	1015	lime	2605	red rock	3500
sand 5 BW	1022	shale blue	2685	lime brkn	3510
lime	1027	lime	2703	lime sft red cave	3528
salt	1365	lime & shale blue	2720	shale	3537
salt, lime shells &		lime	2740	lime white	3541
shale blue	1445	shale blue	2750	sand	3542
shale blue	1470	lime brkn	2757	3000' oil 3543-45'	
lime	1472	U.R. 10" 1,710,000' Gas		Deepened 5' no increase	
shale blue	1477	at 2757'		lime	3550
lime	1530	sdv lime	2780	44 bbls oil in 5 hrs.	
lime rotten & shale	1570	sdv lime	2835	5" perforated liner to	
shale brown	1595	Water 10" U.R. to 2519'		bottom.	
shale brown & blue	1650	2,800,000 show gas		3550= 3555' cable	
lime brkn	1675	sdv lime	2845	Correction	
shale brown	1690	10" U.R. to 2836'		lime	3599
lime brkn	1730	Carrying 7 BW			
lime	1750	lime	2855	Total Depth	3599
sdv lime 2 BW	1770	lime	2900		
sdv lime	1800	sdv lime	2933		
lime	1810	1400' of water			
sand 15 BW	1830	lime	3003		
shale blue	1875	lime	3082		
lime	1385	shale black	3098		
shale blue	1935	lime	3105		
shale brown	1955	shale blue & lime	3108		
lime	1960	lime	3112		
red rock & shale blue	1975	8" at 3111'			
lime	1995	red rock	3160		
shale brown	2035	shale blue	3180		
lime	2043	sdv shale blue	3218		
lime brkn & sdv		sdv lime	3227		
shale HW	2047	shale brown	3235		
shale U.R. 10"	2050	shale blue	3245		
lime	2065	lime	3255		
red rock & lime		8" U.R. to 3253'			
shells	2105	lime	3268		
red rock	2120	30 bbls 38 gravity oil			
shale blue	2160	lime	3270		