

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
245 North Water
WICHITA, KANSAS 67202

Rev. 6-3-74
FORM CP-1

RECEIVED
STATE CORPORATION COMMISSION

APR 20 1982

WELL PLUGGING APPLICATION FORM
File One Copy

API Number 15 - 185 - 21,580 (of this well)
Lease Owner L. D. Davis
Address R. R. 1 Box 183 B Great Bend, Kansas 67530
Lease (Farm Name) AHNERT Well No. 1
Well Location 100' South
SW SE NE Sec. 10 Twp. 22 S Rge. 12 (E) (W) X
County STAFFORD Total Depth 3640 Field Name
Oil Well Gas Well Input Well SWD Well Rotary D & A XX
Well Log attached with this application as required Yes
Date and hour plugging is desired to begin 9:30 A.M. April April 9, 1982

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

Don Popp Address Hoisington, Kansas 67544

Plugging Contractor License No.

Address

Invoice covering assessment for plugging this well should be sent to:

Name L. D. Davis

Address R. R. 1 Box 183 B Great Bend, Kansas 67530

and payment will be guaranteed by applicant or acting agent.

Signed: Don Popp
Applicant or Acting Agent

Date: April 15, 1982

9/30/98

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION

FORM CP-1

Rev. 03/92

130 S. Market, Room 2078
Wichita, Kansas 67202

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API #: 15-185-215800001 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate sp or completion date

WELL OPERATOR: Rupe Oil Company, Inc. KCC LICENSE # 5047
(owner/company name) (operator's)

ADDRESS: P.O. Box 783010 CITY: Wichita

STATE: Kansas ZIP CODE 67278 CONTACT PHONE: 316-262-3748

LEASE: Ahnert "OWWO" WELL#: #1 Section 10 Township 22s Range 12w

100' South of Sw Se Ne SPOT LOCATION/QQQQ COUNTY: Stafford

2410 FEET (in exact footage) FROM North LINE OF SECTION (NOT Lease Line)

990 FEET (in exact footage) FROM East LINE OF SECTION (NOT Lease Line)

Check One: Oil Well Gas Well D&A XX SWD/ENHR WELL Docket #
CONDUCTOR CASING SIZE None SET AT CEMENTED WITH SACKS
SURFACE CASING SIZE 8-5/8" SET AT 290' CEMENTED WITH 300 SACKS
PRODUCTION CASING SIZE None SET AT CEMENTED WITH SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS:

ELEVATION 1846 G.L. 1855 K.B. T.D. 1029 PBDT Anhydrite Depth
(Stone Corral Formation)

CONDITION OF WELL: GOOD XX POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING:

Heavy mud from 1029' to 600' then 50 sacks, then heavy mud to 310' then 50 sacks,

then heavy mud to 40' then 10 sacks. 10 sacks in the rathole and 15 sacks in the

mousehole. Used 60/40 Poz, 6% Gel for plugging. Started plugging well at 11:45 pm

on 08-26-98. Plug down at 2:00 am on 08-26-98 by Allied. Ticket # 2510.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes (YES,NO) IS ACO-1 FILED? ? (YES,NO)

If not explain why?

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS
OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Name: Vaughn Thompson/Steve E. McClain Phone#: (316) 672-9508

Address: P.O. Box 1006 City: Pratt State: Kansas

PLUGGING CONTRACTOR: Sterling Drilling Company KCC LICENSE #: 5142

(company name) (contractor's)

Address: P.O. Box 1006 City: Pratt State: Kansas Zip 67124

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Plugged well at 2:00 am on August 26, 1998.

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY: Operator X Agent

DATE: 08/26/98 AUTHORIZED OPERATOR OR AGENT:

[Signature]
(signature) Steve E. McClain, Agent for Operator

Sterling Drilling Company, Rig #4

Box 1006, Pratt, Kansas 67124-1006
Office Phone (316) 672-9508, Fax 672-9509

SAMPLE LOG

Ahnert "OWWO" #1

LOCATION: 100' South of Sw Se Ne
API: 15-185-215800001

Section 10 T 22s R 12w
Stafford County, Kansas

OWNER: Rupe Oil Company, Inc.
CONTRACTOR: Sterling Drilling Company, Rig #4

COMMENCED: 25-Aug-98
COMPLETED: 26-Aug-98

TOTAL DEPTH: **DRILLER** 1029 FEET
LOGGER Not logged FEET

Ground Elevation: 1846
KB Elevation: 1855

LOG

0 -	40 FEET	Cement
40 -	180 FEET	Open Hole
180 -	225 FEET	Cement stringers
225 -	310 FEET	Cement
310 -	1029 FEET	Redbeds to RTD

CASING RECORDS

290' of 8-5/8" surface casing in place.

Plugged well as follows:

Heavy mud from 1029' to 600' then 50 sacks, then heavy mud to 310' then 50 sacks, then heavy mud to 40' then 10 sacks. 10 sacks in the rathole and 15 sacks in the mousehole. Used 60/40 Poz, 6% Gel for plugging. Started plugging well at 11:45 pm on 08-26-98. Plug down at 2:00 am on 08-26-98 by Allied. Ticket # 2510.

DEVIATION SURVEYS

None Taken