

21-22-13W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock,
Wichita, Kansas

Company- SUNRAY OIL CORPORATION
Farm- Hahn No. 1

SEC. 21 T. 22 R. 13W
SW SW NE

Total Depth. 3839
Comm. 11-6-52 Comp. 11-22-52
Shot or Treated.
Contractor. Mouser Drilling Co.
Issued. 3-14-53

County Stafford
KANSAS



CASING:
8 5/8 278'
5 1/2 3837'

Elevation. 1904

Production. Phys. 16 BO, no wtr

Figures indicate Bottom of Formations.

cellar	5
sand	100
sand & shale	160
sand	220
shale	295
shale & shells	845
red bed & shale	1200
salt	1235
shale & shells	1555
shale & lime	2250
lime	2375
lime & shale	2980
lime	3275
shale & lime	3410
lime	3705
cherty conglomerate	3720
lime & chert	3745
chert	3779
lime & shale	3805
shale	3825
shale & lime	3836
Arbuckle	3839
Total Depth	

TOPS:	
Topeka	2890
Heebner	3278
Toronto	3298
Brown lime	3406
Lansing	3430
Base KC	3659
Marmaton	3668
congl. Chert.	3710
Viola	3733
Simpson shale	3776
Simpson sand	3794
Arbuckle	3836