

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas


25-22-13W

B & R DRIG.CO-HOOPER-BYRNE
Hammeke No. 1.

SEC. 25 T. 22 R. 13 W
CNE SW

Total Depth. 3803'
Comm. 9-21-43 Comp. 10-15-43
Shot or Treated.
Contractor.
Issued. 11-6-43

County. Stafford



CASING:
8 5/8" 320' Cem.

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

shale	230
sand & shale	270
sand	285
shale red rock	730
anhydrite	760
shale & shells	1235
salt & shale	1420
anhydrite & shale	1435
shale & shells	1525
anhydrite & shale	1735
sdv lime	1835
sdv lime & shale	1920
sdv lime & sand	2040
sdv lime	2070
lime & shale	2265
lime	2285
lime & shale	2675
lime brkn & shale	2735
lime & shale	2968
lime Topeka	2995
lime	3100
lime & shale	3125
lime	3225
lime shale & iron	3240
lime	3283
shale	3340
shale & lime	3390
shale	3393
lime	3615
lime & shale	3650
conglomerate	3665
lime & chert	3675
Viola chert	3700
lime & chert	3705
Viola lime	3713
Viola lime & chert	3714
Simpson shale	3740
shale	3754
sand	3757
shale	3778
Arbuckle lime	3803
Total Depth.	

Tops: Topeka(driller)	RTM
Lansing Brown	3366
Lansing White	3391
Cherty Viola	3673
Simpson Shale	3725
Simpson Dolomite	3736
Simpson Sand	3751-57
Arbuckle	3778

sh oil 2970-85