


26-22-13W

STANOLIND OIL & GAS CO.
 A.E. Ahnert No. 2.

SEC. 26 T. 22 R. 13 W
 CN $\frac{1}{2}$ NW SE
 2310' N SL 660' E WL SE $\frac{1}{4}$

Total Depth. 3852'
 Comm. 2-19-43 Comp. 3-24-43
 Shot or Treated.
 Contractor.
 Issued. 5-8-43 Rotary O-3852

County. Stafford



CASING:
 13" 244' Cem.

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

cellar	4'5"	Rotary Core #1 Rec. 5' 3565-72	
sand	75	all wh fine cryst	
shale & shells	275	limestone w/ slight	
red rock	405	porosity in scattered	
red bed & shale	625	spots, bleeding blk	
anhydrite	640	oil	
shale & shells	1305	Rotary Core #2 Rec. 2' 3762-64	
shale	1370	3762-63 $\frac{1}{2}$ gy dense dolomite	
shale & shells	1555	w/ green shale strks	
sd lime & shale	1630	3763 $\frac{1}{2}$ -64 fine cryst dolo.	
lime brkn	1700	gy. Slight porosity,	
lime	1820	slight saturation	
lime brkn	1865	Rotary Core #3 Rec. 2' 3764-67	
lime	2015	gy fine cryst dolo. 3764-66	
lime brkn	2030	light porosity & stain.	
shale sdy	2040	3766-67 fair porosity,	
lime brkn	2200	bleeding blk oil. Took	
lime brkn & shale	2275	drill stem test w/ packer	
shale & lime	2400	set from 3758-80 open	
lime brkn & shale	2470	1 hr. Recovered 20'	
shale & lime	2615	rotary mud w/ very slight	
shale & lime shells	2685	show oil	
shale	2715	Rotary Core #4 Rec. 6' 3767-77	
lime	2760	3767-69 tan fine cryst. dolo-	
lime & shale	2785	oolitic. Good porosity.	
shale & brkn lime	2870	Fair saturation. 3769-72	
lime brkn	2930	no porosity, no saturation.	
lime cherty	2945	3772-76 tan fine cryst.	
lime brkn & shale	2960	dolomite. Good porosity.	
shale	2980	Fair saturation. 3767-77	
lime brkn	3045	gy, dense dolomite. No	
lime	3140	porosity, no saturation.	
lime brkn	3180		
lime very firm	3230		
lime	3270		
lime brkn & shale	3320		
shale	3410		
lime	3621		
shale	3630		
lime	3660		
lime brkn & shale	3675		
lime brkn	3681		
chert	3687		
		cherty lime	3701
		chert	3711
		shale	3712
		sd shale	3738
		shale	3768
		lime	3777
		lime & shale	3792
		lime	3852
		Total Depth.	
		Tops:	
		Lansing	3400
		Simpson	3711
		Arbuckle	3760