

26-22-13W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- BROOKS PIERCE ET AL
Farm- Spatz No. 2

SEC. 26 T. 22 R. 13W
NW SE SE

Total Depth. 3760'
Comm. 5-29-65 Comp. 6-8-65
Shot or Treated.
Contractor. Donald T. Ingling
Issued. 4-9-66

County Stafford
KANSAS



Elevation. 1887' RB

Production. 25 BOPD, NW

CASING:

8 5/8" 280' cem w/250 sx.
4 1/2" 3754' cem w/125 sx.

Figures Indicate Bottom of Formations.

surface clay	40
sand	200
red rock	280
shale & red rock	710
Anhydrite	745
shale & shells	1640
lime & shale	1960
lime & sand strks	1975
sand & lime strks	1990
lime	2010
lime & shale	2160
shale & lime	2335
lime & shale	2645
shale & lime	2850
lime	3255
lime & shale	3265
shale & lime strks.	3368
lime	3581
lime & shale	3640
lime	3680
lime & chert	3700
shale & sand	3715
sand & shale	3752
lime - Arbuckle	3760
Total Depth	

TOPS: SAMPLE

Anhydrite	710
Heebner	3230
Brown Lime	3368
Lansing	3387
Viola	3646
Simpson	3694
Arbuckle	3752