

28-22-13W

WELL LOG BUREAU-KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. STANOLIND OIL & GAS CO.
Farm-Alice Hingey No. 1

SEC. 28 T. 22 R. 13W
SW NW SW
1650' N of SL, 330' E of WL
SW $\frac{1}{4}$
County Stafford
KANSAS

Total Depth. 3860 PBD 3834
Comm. 12-19-52 Comp. 1-20-53
Shot or Truted.
Contractor.
Issued. 3-14-53

CASING:

8 5/8 set at 678 w/ 600 sx cement
5 1/2 set at 3858' w/ 150 sx cement

Elevation. 1909 RB

Production. 40 BO, 24 BW

Figures Indicate Bottom of Formations.

surface clay	100
sand	325
shale	605
shale & sand	678
red bed & anhydrite	800
shale & shells	1600
lime	1820
lime & shale	2010
lime	2045
lime & shale	3180
lime	3289
shale	3416
Brown lime	3440
lime	3719
conglomerate	3737
cherty conglomerate	3780
Viola conglomerate	3798
cherty conglomerate	3804
Simpson	3809
shale	3857
lime, oil shows	3860 RTD
Total Depth PB 3834	

Schlumberger T. D. 3861

TOPS:

Heebner	3289
Iatan	3416
Lansing KC	3440
Conglomerate	3719
Viola	3751
Simpson	3804
Arbuckle	3857

Producing from perforations
3564-3568
3595-3601
3622-3630