

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- ANSCHUTZ DRILLING CO.
Farm- Weiszbrod No. 5

SEC. 1 T. 22 R. 13W
NE NW NW

Total Depth. 5685
Comm. 1-3-54 Comp. 1-14-54
Shot or Treated.
Contractor.
issued. 3-20-54

County Stafford
KANSAS



CASING:

8 5/8" 278' cem. w/225 sx
5 1/2" 3657'

Elevation. 1878' DE

Production. Pot. 77 BOPD & 9% wtr

Figures indicate Bottom of Formations.

sand & shale	0-230-
shale & red bed	700
anhydrite	735
shale & shells	1250
salt & shells	1355
shale & lime	1865
lime	1885
sandy lime	1950
lime & shale	2360
shale	2640
shale & lime	2690
lime	3175
shale & lime	3300
lime	3652
ar buckle	3656 RTD
ar buckle	3653
Total Depth	

TORE: (KB)

Hoebner Shale	3169
Toronto Lime	3193
Iatan Lime	3297
Lansing-Kansas City	3316
Base Kansas City	3545
Conglomerate	3556
Viola Chert	3571
Simpson Shale	3604
Ar buckle Dolomite	3653

COMPLETION DATA:

Drilled Shoe - no show
DD 3665-68 - 1/2 BOPH
DD 3680-82 - 850' FU 1 3/4 hrs.
1000' FU 3 1/4 hrs.,
DD 3683 - Swb 2 1/2 BOPH 6 hrs.
500 acid 3680-82 swb. 5 BOPH
cont'd swbg. - dec. to 3 BOPH
500 acid 3665-68.

Shots 18/3680-83
500 acid swbg. 5.85 BOPH 10 hrs.

D.S.T. open 21 min., gas in 3 min.,
flowed oil in 19 min., IFP 820#,
FFP 930#, SIP 1080# in 15 min.,
HYD 1920#.