

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- PETROLEUM, INC.
Farm- Gates "B" No. 1

SEC. 3 T. 22 R. 13W

~~NE SE NE~~
Ne Se Nw

Total Depth. 3760
Comm. 3-9-52 Comp. 3-20-52
Shot or Treated.
Contractor. Garvey Drlg. Co.
Issued. 5-16-53

County Stafford
KANSAS



CASING:

8 5/8" 275' cem. w/175 sx
5 1/2" 3752' cem. w/75 sx

Elevation. 1893 RB

Production. 57 BO & NW

Figures Indicate Bottom of Formations.

sand	180
sand rock	190
sand	220
shale & shells	300
red bed, shale & shells	700
red bed	730
anhydrite	760
shale & shells	1520
lime & shale	2185
shale & shells	2192
shale & lime	2380
shale, lime & shells	2580
shale & shells	2755
lime & shale	3115
lime	3573
shale & lime	3635
cherty congl. & viola	3675
viola	3702
shale & simpson	3711
simpson	3750
lime	3760 RTD
Total Depth	

Tops:

Heebner	3230
Brown Lime	3359
Lansing	3377
Congl.	3635
Viola	3644
Simpson	3701
Arbuckle	3750