

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

Company-BIRMINGHAM-BARTLETT DRILLING CO.
Farm-Schmid No. 1SEC. 5 T. 22 R.13W
SW SE NE

Total Depth. 3771


Comm. 3-5-57

Comp. 3-15-57

Shot or Treated.

Contractor. Birmingham-Bartlett Drilling Co.

Issued. 6-15-57

County Stafford
KANSAS

CASING:
 8 5/8 @ 281' w/ 200 sx cmt.
 5 1/2 @ 3766' w/ 100 sx cmt.

Elevation. 1904 RB

Production. 50 bbls.

Figures indicate Bottom of Formations.

surface clay & sand	100
sand & shale	281
red bed & shells	530
red bed	752
anhydrite	786
shale	1335
shale & shells	1650
lime & shale	2300
shale & shells	2450
shale	2700
lime & shale	2960
lime	3320
sandy shale	3372
lime	3670
Viola chert	3725
shale	3765
lime	3771
Total Depth	

TOPS:

Anhydrite	752
Heebner	3229
Brown lime	3372
Lansing	3383
Conglomerate	3649
Viola	3670
Simpson	3718
Arbuckle	3764

DST #1: 3406-17, open 1 hr. fr. bl.
 rec. 60' GCM, 180' SW, BHP 665#

DST #2: 3452-77, open 1 hr. fr. bl.
 thruout. rec. 390' SW, BHP 1050#

DST #3: 3540-57, open 45 min. wk. bl.
 25 min. rec. 12' mud, BHP 250#

DST #4: 3764-67, open 45 min. wk. bl.
 6 min. rec. 10' mud, BHP 220#

DST #5: 3766-71, open 1 hr. sl. bl.
 rec. 270' oil, BHP 1080#

Oil FU 700'/6 hrs. while bailing
 1 1/2 BOPH or 4 BOPH natural, no wtr.
 500 gal acid.POP.