

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company-BIRMINGHAM-BARTLETT DRILLING CO.  
Farm-Schmidt "A" No. 1

SEC. 5 T. 22 R. 13W  
C N/2 NE SE

Total Depth. 3778  
Comm. 4-18-57 Comp. 4-28-57

County Stafford  
KANSAS

Shot or Treated.  
Contractor. Birmingham-Bartlett Drilling Co.  
Issued. 6-15-57



8 5/8 @ CASING:  
281' w/ 200 sx cmt.

Elevation. 1904 RB

Production. Dry

Figures indicate Bottom of Formations.

surface clay & sand	100
sand & shale	220
shale	281
hard sand	295
red bed & shells	759
anhydrite	788
shale & shells	1550
shale	1650
lime & shale	2285
shale & shells	2625
lime & shale	2885
lime	3242
shale & lime	3375
brown lime	3386
Lansing-KC lime	3405
lime	3645
shale	3673
Viola	3681
chert	3700
Viola chert	3723
sandy shale	3750
shale	3774
Arbuckle	3778
Total Depth	

TOPS:

Anhydrite	759
Heebner	3242
Brown lime	3375
Lansing	3386
Conglomerate	3654
Viola	3674
Simpson	3724
Arbuckle	3774

DST #1: 3406-18, open 1 hr. wk. bl. thruout, rec. 185' muddy SW w/ few specks of oil, IFP 0#, FFP 140#, BHP 905#.

DST #2: 3650-81, open 1 hr. very wk. bl. 7 min. rec. 43' mud w/ very few oil specks, BHP 110#

DST #3: 3775-78, open 2 hrs. rec. 540' sulphur wtr. BHP 1220#